

**CITY CLERK
ORIGINAL**



C-10031
06/09/2015

PROJECT SPECIFICATIONS AND CONTRACT DOCUMENTS

PROJECT NO. 131423

2014/2015 BRIDGE MAINTENANCE REPAIR – VARIOUS LOCATIONS

APRIL, 2015



Expires: 09/30/17

CITY OF GLENDALE

ENGINEERING DEPARTMENT

5850 W. Glendale Avenue, Glendale, Arizona 85301 (623) 930-3630



Memorandum

DATE: April 23rd, 2015
TO: All Plan and Specification Holders
FROM: Engineering
SUBJECT: PROJECT NO. 131423 – 2014/2015 BRIDGE MAINTENANCE REPAIR –
VARIOUS LOCATIONS – APRIL 2015

ADDENDUM NO. 1

In accordance with the contract documents "Information for Bidders," Page 4, Paragraph 12 CHANGES TO PLANS AND DOCUMENTS, the following revisions to the plans and specifications shall become a part of the contract documents and the bidder shall acknowledge receipt thereof as directed in Paragraph 13 of the Information for Bidders.

Corrections / Clarifications –

- Please note: Page 5, Item No. "16. TIME OF COMPLETION", sentence three (3) shall be revised TO "ONE HUNDRED AND TWENTY (120) consecutive calendar days..."
- Contractor shall protect in place all areas impacted under bridge removal areas at all times during deck edge removal activities.
- REMOVE page eight (8) of specifications "Bid Schedule" with REPLACE with the attached revised "Bid schedule (rev.)"
- INSERT "Special Provisions for BID ALTERNATE No. 1" – nine (9) pages total including sealed coversheet
- INSERT "Bid Alternate No. 1, Dysart Road Bridge Approach Slab Repairs" 8 ½ X 11 plan sheets – three (3) pages total
- NOTE: 11X17 PLAN SHEETS FOR BID ALTERNATE NO. 1 ARE AVAILABLE FOR PICK UP at the City of Glendale Engineering Counter – Suite 315, 5850 West Glendale Avenue, Glendale AZ 85301.

PLEASE SEE ATTACHED -

**THIS ADDENDUM NO. 1
INCLUDES 14 SHEETS TOTAL
INCLUDING THIS MEMORANDUM
COVERSHEET**



EXPIRES: 9/30/2017

PROJECT NO. 131423
2014/2015 Bridge Maintenance Repair - Various Locations
BID SCHEDULE (rev.)

ITEM	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL BID
1	Mobilization / Demobilization (ALL SITES)	1	LS		
2	Traffic Control (ALL SITES)	1	LS		
21	Owners Allowance for Construction Contingencies	1	LS	\$30,000.00	\$30,000.00
<i>Structure No. 9301</i>					
3	Partial Bridge Removal (Overhang)	1	LS		
4	Structural Concrete (Class S - 4500psi)	87	CY		
5	Replace Low Clearance Signs	2	EA		
6	Reinforcing Steel	29,600	LB		
22	Asbestos bearing pad removal (handling / proper disposal)	1	LS		
<i>Structure No. 9443</i>					
7	Barrier and Sidewalk Removal	1	LS		
8	Structural Concrete (Class AA - 4000psi)	7	CY		
9	Reinforcing Steel	1,100	LB		
<i>Structure No. 9885</i>					
10	Replace Missing Pedestrian Rail	1	LS		
11	Replace Missing/Damaged Pedestrian Rail Pickets (10)	10	EA		
12	Clean Clogged Bridge Deck Drains	1	LS		
13	Secure Object Marker (SE Corner)	1	EA		
<i>Structure No. 9886</i>					
14	Partial Barrier Removal	1	LS		
15	Salvage and Reinstall Light Pole	1	LS		
16	Replace Missing Top Rail	320	LF		
17	Structural Concrete (Class AA - 4000psi)	2	CY		
18	Reinforcing Steel	105	LB		
19	Clean Clogged Bridge Deck Drains	1	LS		
20	Erosion Remediation	15	CY		
				TOTAL BASE BID	

PROJECT No. 131423 - 2014/2015 BRIDGE MAINTENANCE REPAIR - BID ALTERNATE NO. 1

ITEM	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL BID
BA1	Mobilization / Demobilization	1	LS		
BA2	Traffic Control	1	LS		
BA3	Partial approach slab surface removal / preparation / replacement (per specifications)	212	SF		
BA4	Approach slab(s) Epoxy Healer / Sealer (per specifications)	2,040	SF		
BA5	Owners Allowance for Construction Contingencies	1	LS	\$5,000.00	\$5,000.00
				TOTAL BID ALTERNATE NO. 1	

**CITY CLERK
ORIGINAL**



SPECIAL PROVISIONS

For

BID ALTERNATE NO. 1

Dysart Road Bridge Approach Slab Repairs

City of Glendale Project No. 121332

(For use with the Maricopa Association of Governments Uniform Standard Specifications for Public Works Construction, 2014 Edition and Revisions to Date)



CONTENTS

- LOCATION OF THE WORK2
- PROPOSED WORK.....2
- SECTION 107 LEGAL REGULATIONS AND RESPONSIBILITY TO PUBLIC.....3
- SP-1 MOBILIZATION.....4
- SP-3 CONCRETE PATCH5
- SP-4 EPOXY HEALER/SEALER.....7

LOCATION OF THE WORK: This project is located at: Dysart Road Bridge over Dysart Drain, approximately ½ mile north of Glendale Avenue, City of Glendale, Maricopa County, Arizona. The work is limited to the bridge approach slabs.

PROPOSED WORK: The work consists of removing and replacing areas of delaminated concrete on the bridge approach slabs and applying an epoxy healer/sealer to the bridge approach slabs. The work requires traffic control during construction.

SECTION 107 LEGAL REGULATIONS AND RESPONSIBILITY TO PUBLIC

107.2 PERMITS, add the following:

The Contractor shall comply with all **City of Glendale** permitting requirements.

The Contractor shall obtain a no-fee Right-of-Way Permit and a Barricade Permit from the City of Glendale in order to close any traffic lanes or sidewalks on Dysart Road. All restrictions require a Barricade Permit. The Contractor **MUST** use a barricade company that has been certified to set up and pick up barricades within the City of Glendale right-of-way. Each traffic control plan shall be submitted at least three (3) business days prior to the restriction through the Transportation Services online application process, which can be found at www.glendaleaz.com/transportation/TrafficControlForm.cfm.

SP-1 MOBILIZATION:

A. DESCRIPTION

The work under this section shall consist of mobilizing/demobilizing the Contractor's personnel, equipment, supplies and incidentals required for the performance of the work on the project, as well as preparatory work and operations prior to the commencement of the work on the project site. See MAG Section 109.10 for additional information.

B. MEASUREMENT

Mobilization will be measured by the lump sum as a single complete unit of work.

C. PAYMENT

Mobilization will be paid at the contract lump sum price. The City will compensate the Contractor for a single round trip mobilization/demobilization. Payment shall be made in equal one-third portions. The first payment will be paid with the Contractor's initial billing. The second payment will be paid when the total payments to the Contractor for the pay items, exclusive of payments for mobilization/demobilization, equal greater than one-half of the initial contracted amount, exclusive of mobilization/demobilization. The remaining one-third payment will be paid as part of the final payment due to the Contractor.

SP-3 CONCRETE PATCH:

A. DESCRIPTION

The work under this section shall consist of identifying, marking, removing, and disposing of all existing delaminated concrete on the bridge approach slabs, thoroughly cleaning the repair areas, and placing new patches as detailed on the plans, according to these Special Provisions, in accordance with the manufacturer's recommendations, and as directed by the Engineer.

B. MATERIALS

All areas to be patched shall be filled with SikaQuick 2500 rapid hardening repair mortar, or an approved equal. The patch material shall have a minimum concrete strength of 4,000 psi.

C. CONSTRUCTION REQUIREMENTS

Locations and dimensions of delaminated concrete limits shown on the plans are approximate. Exact limits shall be determined during construction by the Contractor and the Engineer by sounding the concrete with a hammer. Any additional areas of delaminated concrete shall be marked for removal.

Removal of existing concrete shall conform to MAG Section 350.

The perimeter of each delaminated concrete area shall be saw cut to a depth of ½ inch to create a clean edge on all sides. Care shall be taken to avoid cutting into the existing reinforcing steel. The Contractor shall be especially careful, as the reinforcing steel is likely to have less than the typical 2 ½ inches of clear cover.

Concrete removal shall extend from the top of the approach slab to the mid depth of the top reinforcing bar as a minimum. The depth of removal shall be deeper if required, until sound concrete is reached.

All concrete removal shall be performed with sufficient care as to leave the remaining portion of the structure undamaged. All damage to the existing concrete which is to remain in place shall be repaired to a condition equal to that existing prior to the beginning of the removal operations. The repair of existing concrete damaged by the Contractor's removal operations shall be at no additional cost to the City.

Existing steel reinforcement that is to be incorporated into the new work shall be protected from damage and shall be thoroughly straightened and cleaned of all adhering material before being embedded in new concrete. Any loose reinforcement shall be securely tied to the other remaining existing reinforcement prior to placing the new patch.

Damaged steel reinforcement shall be cut off, and a new dowel shall be installed for every damaged bar at no additional cost to the City.

All concrete removed shall become the property of the Contractor and shall be immediately removed from the project site. All concrete removed shall be contained to prevent debris from falling into the channel. Fallen debris shall be immediately picked up for disposal. Access to the channel shall be coordinated with the City.

All areas to be patched shall be thoroughly cleaned by water blasting or sand blasting to remove all dirt, oil, grease, and other bond-inhibiting materials. The surface shall be an exposed aggregate surface with a minimum surface profile of 1/8 inch +/- . The surface shall then be swept with high pressure air to remove all dirt, debris and loose particles. Prior to installing the patch material, the surface shall be saturated surface dry (SSD). Surface preparation shall also comply with the manufacturer's recommendations for the chosen patch material. The patch material shall be applied and finished in accordance with the manufacturer's recommendations.

C. MEASUREMENT

Concrete Patch will be measured by the square foot.

Saw cutting of concrete will not be measured but will be considered incidental to the Concrete Patch item.

D. PAYMENT

Concrete Patch will be paid at the contract unit price per square foot.

SP-4 EPOXY HEALER/SEALER:

A. DESCRIPTION

The work under this section shall consist of installing an epoxy healer/sealer to the bridge approach slabs as detailed on the plans, according to these Special Provisions, in accordance with the manufacturer's recommendations, and as directed by the Engineer.

B. MATERIALS

The epoxy healer/sealer shall be Sikadur 55 SLV or an approved equal. The healer/sealer shall be "super low viscosity," to ensure penetration into the existing cracks in the concrete.

C. CONSTRUCTION REQUIREMENTS

Prior to construction, the chosen epoxy healer/sealer and the application method shall be approved by the Engineer. The Contractor shall submit for approval by the Engineer, the product data sheets (PDS), the material safety data sheets (MSDS), and detailed procedures of the application method, including the method for applying the healer/sealer into any large cracks that are present.

Prior to installation of the epoxy healer/sealer, the top surface of the approach slabs shall be thoroughly cleaned. The surface shall be cleaned by shot blasting, sand blasting, or mechanical abrasion. Water blasting is not acceptable. The surface shall then be swept with high pressure air to remove all dirt, debris and loose particles. The surface shall be dry.

The work shall be conducted in a continuous operation, with the epoxy healer/sealer application immediately following the surface preparation.

The epoxy healer/sealer shall be applied according to the manufacturer's recommendations.

Any cracks larger than 0.002 inches in width shall be considered "large cracks" and shall be pretreated. The epoxy healer/sealer shall be applied directly into the large cracks using hand held bottles or another method recommended by the manufacturer and approved by the Engineer. Cracks larger than 1/8 inch wide shall be filled with oven-dried sand prior to pretreating with epoxy healer/sealer. The large cracks shall be filled and refilled until refusal is encountered. There shall be no separate payment for filling the large cracks. Payment shall be included in the square foot price.

Immediately after pretreating the large cracks, the epoxy healer/sealer shall be applied over the approach slabs. The epoxy healer/sealer shall be applied in generous amounts, such that puddles remain on the surface for several minutes. The epoxy

healer/sealer shall then be spread over the area using flat squeegees or brooms. After allowing the epoxy healer/sealer to penetrate into the cracks and the concrete, any excess shall be removed with a roller, leaving no visible surface film.

After treatment, the contractor shall wait the amount of time recommended by the manufacturer before broadcasting sand over the area. The treated area shall be broadcast with an oven-dried silica sand or similar sand. The sand shall be distributed evenly over the surface at a rate of 30-40 lbs/100 square feet. The surface shall be allowed to cure according to the manufacturer's recommendations before removing excess sand. Excess sand shall be removed prior to opening to traffic.

The approved traffic control plan may require that the epoxy healer/sealer be applied in phases while maintaining traffic on other parts of the structure. In this case, the Contractor shall submit the method of applying the epoxy healer/sealer in phases for approval prior to construction.

D. MEASUREMENT

Epoxy Healer/Sealer will be measured by the square foot.

E. PAYMENT

Epoxy Healer/Sealer will be paid at the contract unit price per square foot.

CITY OF GLENDALE


GLENDALE, ARIZONA

121332

BID ALTERNATE NO. 1


DYSART ROAD BRIDGE

APPROACH SLAB REPAIRS



GLENDALE

- MAYOR**
JERRY P. WIEBERS
- CITY COUNCIL**
JAMIE ALDAMA
SAMUEL U. CHAVIRA
IAN HUGH
GARY D. SHERWOOD
LAUREN TOLMACHOFF
BART TURNER
- ACTING CITY MANAGER**
RICHARD A. BOWERS
- CITY CLERK**
PAMELA HANNA
- ACTING CITY ATTORNEY**
MICHAEL D. BAILEY



RECORDED DRAWING
I certify that the locations, elevations, depths and record drawing comments accurately reflect the existing field conditions and materials actually used during construction. This information is based on periodic field observations and the contractor's representations of the facilities as constructed.


NAME _____ DATE _____ (SEAL)
REGISTRATION NO. _____ EXP. DATE _____
REV'D. BY _____
CONSTRUCTION ENGINEER

PLANS ACCEPTANCE
The City of Glendale accepts these plans for construction, as being in general compliance with prior preparation requirements of the City. Responsibility for the completeness and accuracy of the plans and related design resides with the Engineer and the Engineering Firm of Record.


DATE 4/23/2015
CITY ENGINEER
DEPUTY PUBLIC WORKS DIRECTOR - TRANSPORTATION

SHEET INDEX

SHT. NO.	DESCRIPTION
1	COVER SHEET
2	PLAN AND GENERAL NOTES
3	CONSTRUCTION DETAILS



ENGINEER GENERAL NOTES
 DESIGN TO THE AMERICAN STANDARDS SPECIFICATIONS FOR PUBLIC WORKS
 ALL WORK SHALL BE IN ACCORDANCE WITH THE AMERICAN ASSOCIATION OF ENGINEERS (AASHTO) DATED 2012 WITH
 REVISIONS THROUGH 2012 AND THE PROJECT SPECIAL PROVISIONS.
 DESIGN IS IN ACCORDANCE WITH AASHTO LIFT BRIDGE DESIGN SPECIFICATIONS, 2012 AND REVISIONS TO
 DATE.
 DIMENSIONS SHALL NOT BE SOLED FROM DRAWINGS.



PLAN
 SCALE 1" = 10'

- LEGEND**
- DETAIL NUMBER
 - TITLE/DETAIL MARKER
 - SHEET NUMBER
 - SECTION LETTER
 - SHEET NUMBER
 - ELEVATION LETTER
 - SHEET NUMBER
 - INDICATES AREA TO RECEIVE EPOXY HEALY/SEALER

CITY OF GLENDALE
 ENGINEERING DEPARTMENT
 GLENDALE, ARIZONA 85301 (602) 930-0930

121332
 DYSART ROAD BRIDGE
 APPROACH SLAB REPAIRS
 PLAN AND GENERAL NOTES

Scale: as Shown
 602.263.1100
 SHT. 3 of 3

Mar 26, 2015 - 2:53pm

Project: 121332 - Dysart Road Bridge Approach Slab Repairs




Project	121332
Client	CITY OF GLENDALE
Contract	CONSTRUCTION DETAILS
Drawn	JRR
Checked	FJ
Scale	As Shown


121332
DYSART ROAD BRIDGE
APPROACH SLAB REPAIRS

PREMIER
 CONCRETE REPAIR SYSTEMS


- REPAIR NOTES:**
1. LOCATIONS AND DIMENSIONS OF DELAMINATED CONCRETE ARE APPROXIMATE. EXACT LIMITS SHALL BE DETERMINED DURING CONSTRUCTION BY THE CONTRACTOR AND THE ENGINEER.
 2. DELAMINATED CONCRETE AREAS SHALL BE SAW CUT AND REMOVED AS SHOWN ON THIS SHEET. THE REMOVAL SHALL BE AT LEAST THE FULL WIDTH AND DEPTH OF THE DELAMINATION. THE DEPTH OF REMOVAL SHALL BE DEEPER IF REQUIRED TO REACH SOUND CONCRETE.
 3. CONCRETE REMOVAL SHALL BE PERFORMED USING HAMMERS NO GREATER THAN 15 POUNDS. CARE SHALL BE EXERCISED SO THAT EXISTING REINFORCING STEEL IS NOT DAMAGED. ANY DAMAGE SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE AND AS DIRECTED BY THE ENGINEER.
 4. UNSOUND CONCRETE AROUND THE REPAIR AREAS, BEYOND THE LIMITS SHOWN ON THIS SHEET SHALL BE IDENTIFIED BY THE CONTRACTOR AND VERIFIED BY THE ENGINEER. THE COST IS CONSIDERED INCIDENTAL TO THE REPAIR WORK. ANY ADDITIONAL UNSOUND CONCRETE AREAS, OTHER THAN IDENTIFIED AREAS, SHALL BE IDENTIFIED BY THE CONTRACTOR AND VERIFIED BY THE ENGINEER. THE COST FOR THIS ADDITIONAL REPAIR SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR CONCRETE PATCH ITEM.
 5. CLEARED REPAIR AREAS SHALL BE FILLED WITH SQUICK 2500 RAPID HARDENING REPAIR MORTAR OR AN APPROVED EQUAL. THE PATCH SHALL HAVE A MINIMUM CONCRETE STRENGTH OF 4,000 PSI. THE PATCH SHALL BE CURED AND PREPARED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS. THE CONTRACTOR SHALL PROVIDE A PROVISION FOR ADDITIONAL INFORMATION.
 6. AFTER ALL DELAMINATED CONCRETE AREAS HAVE BEEN REPAIRED AND CURED, EPOXY BEHAVIOR AS SHOWN ON THIS SHEET, SAND SHALL BE BROADCAST OVER THE EPOXY HEALER/SEALER TO PROVIDE SLIP RESISTANCE. THE APPLICATION OF THE EPOXY HEALER/SEALER SHALL NOT BEGUN UNTIL THE REPAIR MORTAR HAS FULLY CURED. THE CONTRACTOR SHALL PROVIDE A PROVISION FOR ADDITIONAL INFORMATION. SEE SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION.



DELAMINATED CONCRETE REPAIR - DETAIL
 N.T.S.



SECTION A
 N.T.S.



DELAMINATED CONCRETE LOCATIONS - PLAN
 SCALE: 1" = 5'

Mar 28, 2015 - 2:55pm

6:\201508-02\CAD\Draw\Schem\1003_Sched_Plan\Construction Details 01.dwg

PROJECT SPECIFICATIONS AND CONTRACT DOCUMENTS

MAYOR

Jerry P. Weiers

COUNCIL MEMBERS

Jaime Aldama

Samuel U. Chavira

Ian Hugh

Gary D. Sherwood

Lauren Tolmachoff

Bart Turner

ACTING CITY MANAGER

Richard A. Bowers

CITY ATTORNEY


Michael D. Bailey

CITY CLERK

Pamela Hanna

CITY ENGINEER

David D. Beard



GLEND~~A~~LE
L

TABLE OF CONTENTS

NOTICE TO CONTRACTORS	1
INFORMATION FOR BIDDERS.....	2
1. ELIGIBILITY OF CONTRACTORS.....	2
2. PROPOSAL	2
3. BID SECURITY	2
4. WITHDRAWAL OF BID.....	3
5. LATE BIDS	3
6. AWARD OR REJECTION OF BIDS	3
7. BIDDERS INTERESTED IN MORE THAN ONE BID	3
8. CONTRACT AND BONDS.....	3
9. INSURANCE REQUIREMENTS.....	3
10. SUBCONTRACTORS' LISTING AND CERTIFICATION OF CONTRACT COMPLIANCE.....	4
11. INTERPRETATION OF PLANS AND DOCUMENTS	4
12. CHANGES TO PLANS AND DOCUMENTS	4
13. ADDENDUM	4
14. ASSIGNMENT OF CONTRACT	4
15. PLANS AND SPECIFICATIONS TO SUCCESSFUL BIDDER	5
16. TIME OF COMPLETION.....	5
17. CITY OF GLENDALE TRANSACTION PRIVILEGE TAX.....	5
18. PRE-BID CONFERENCE.....	5
19. ALTERNATES.....	5
20. APPROVAL OF SUBSTITUTIONS	5
21. USE OF "EQUALS"	5
22. EXAMINATION OF CONTRACT DOCUMENTS AND VISIT SITE	6
23. BIDDERS IN DEFAULT.....	6
PROPOSAL	7
BID BOND	10
SUBCONTRACTOR LISTING AND CERTIFICATION OF CONTRACT COMPLIANCE	11
CONSTRUCTION AGREEMENT	12
PERFORMANCE BOND.....	26
PAYMENT BOND.....	27
CERTIFICATE OF INSURANCE.....	28
CONTRACTOR'S AFFIDAVIT/LIEN WAIVER	30
SUPPLEMENTAL GENERAL CONDITIONS	31
1. GENERAL.....	31
2. DEFINITIONS.....	31
3. PROPOSAL QUANTITIES	31
4. WITHDRAWAL OF PROPOSALS.....	32
5. LOSSES AND DAMAGES.....	32
6. DUST PREVENTION	32
7. EXCESS MATERIAL	32
8. STOCKPILE OF MATERIALS	32
9. REFUSE COLLECTION ACCESS	32

10.	CLEAN-UP.....	32
11.	SHOP DRAWINGS.....	32
12.	PROTECTION OF FINISHED OR PARTIALLY FINISHED WORK.....	33
13.	STATUS OF EMPLOYEES.....	33
14.	LAWS AND REGULATIONS.....	33
15.	PERMITS.....	33
16.	ELECTRIC POWER AND WATER.....	33
17.	SURVEY CONTROL POINTS AND MONUMENTS.....	33
18.	EXISTING UTILITIES.....	33
19.	MAINTENANCE OF IRRIGATION FACILITIES.....	34
20.	OVERHEAD UTILITY LINES AND POLES.....	34
21.	SOUTHWEST GAS FACILITIES EXPOSED DURING CONSTRUCTION.....	34
22.	UNDERGROUND UTILITIES' BEDDING.....	34
23.	SEWER SERVICE LINES.....	34
24.	RIGHTS-OF-WAY.....	34
25.	SUBCONTRACTS.....	34
26.	PRE-CONSTRUCTION CONFERENCE.....	35
27.	OVERTIME.....	35
28.	CONTRACTOR'S CONSTRUCTION SCHEDULE.....	35
29.	CHARACTER OF WORKMEN.....	36
30.	HINDRANCES AND DELAYS.....	36
31.	LIQUIDATED DAMAGES.....	36
32.	PAYMENTS TO CONTRACTOR.....	37
33.	WARRANTY.....	37
	 SPECIAL PROVISIONS.....	 38
1.	SCOPE OF WORK.....	38
2.	DEFINITIONS.....	38
3.	SUSPENSION OF WORK.....	38
4.	COMPLIANCE WITH MANUFACTURER'S INSTRUCTIONS.....	38
5.	TRAFFIC REGULATIONS.....	38
6.	ENERGIZED AERIAL ELECTRICAL POWER LINES.....	40
7.	RECORD DRAWINGS.....	40
8.	CONSTRUCTION MATERIALS SAMPLING AND TESTING.....	40
9.	CASH FLOW REPORT.....	41
10.	ALLOWANCE FOR CONSTRUCTION CONTINGENCIES.....	41
	 CASH FLOW REPORT (EXAMPLE).....	 42

NOTICE TO CONTRACTORS

Sealed bids shall be either mailed to the City of Glendale Engineering Department, 5850 West Glendale Avenue, Glendale, Arizona, 85301, or hand-delivered to the Engineering Department office, third floor, 5850 West Glendale Avenue, Glendale, Arizona, for furnishing all plant, material, equipment and labor, and to complete construction of: **PROJECT NO. 131423 - 2014/2015 BRIDGE MAINTENANCE REPAIR - VARIOUS LOCATIONS**. Project includes various repairs of approximately 6 transportation bridges at various locations. Repairs include, but are not limited to, removal/replacement of structural concrete/steel, repair of signage, guard/pedestrian rail repairs, traffic control and additional miscellaneous work.

Bids must be received by the Engineering Department of the City of Glendale no later than 10:00 AM, APRIL 30, 2015. Any bid received after that time will not be considered and will be returned to the bidder. At that time, the bids will be publicly opened and read aloud in the Engineering Department Conference Room, 5850 West Glendale Avenue, Glendale, Arizona.

A pre-bid conference will be held on APRIL 23, at 10:00 AM, in the Engineering Department Conference Room, 5850 West Glendale Avenue, Glendale, Arizona. Bidders, contractors, and other interested parties are invited to attend this conference which will be conducted by the Owner and Engineer to answer any questions.

Plans, specifications and contract documents may be examined, and copies may be obtained at City of Glendale Engineering Department, 5850 West Glendale Avenue, Glendale, Arizona. A non-refundable charge of \$30 shall be paid for each set of plans and specifications issued from this office.

Each bid shall be in accordance with the plans, specifications and contract documents, and shall be set forth and submitted on the BID DOCUMENTS included with the project specifications book. The BID DOCUMENTS may be removed from the project specifications book and submitted independently of such book. Each bid shall be accompanied by a proposal guarantee, in the form of a certified or cashier's check or bid bond for ten percent (10%) of the amount of bid, made payable to the order of the City of Glendale, Arizona, to insure that the successful bidder will enter into the contract if awarded to him and submit the required Certificate of Insurance, Payment Bond and Performance Bond. All proposal guarantees, except those of the three lowest qualified bidders, will be returned immediately following the opening and checking of proposals. The proposal guarantees of the three lowest qualified bidders will be returned immediately after the contract documents have been executed by the successful bidder. The proposal guarantee shall be declared forfeited as liquidated damages if the successful bidder refuses to enter into said contract or submit the Certificate of Insurance, Payment Bond and Performance Bond after being requested to do so by the City of Glendale, Arizona.

The City of Glendale reserves the right to reject any or all bids or waive any informality or irregularity in a bid. No bidder may withdraw his bid for a period of fifty (50) days after opening and reading of the bids.

The City of Glendale is an equal opportunity employer and minority business enterprises and women's business enterprises are encouraged to submit bids.

CITY OF GLENDALE, ARIZONA

INFORMATION FOR BIDDERS

1. ELIGIBILITY OF CONTRACTORS: When calling for bids for contracts for public work to be performed on behalf of the State or any political subdivision thereof, which will be paid for from public funds, no bid shall be considered for performance of a contract, including construction work which is not submitted by a bidder duly licensed as a contractor in this State. No bid shall be awarded to any contractor or entity not authorized to do business in the State of Arizona by the Arizona Corporation Commission, as required by statute.

2. PROPOSAL: Bids to receive consideration shall be made in accordance with the following instructions:

(a) Before submitting a bid, bidders shall carefully examine the plans and specifications and contract documents, visit the site of the work, fully inform themselves as to all existing conditions and limitations.

(b) Bids shall be submitted on the "PROPOSAL" forms provided and delivered to the City of Glendale Engineering Department on or before the day and hour set in the "NOTICE TO CONTRACTORS," as published. Bids shall be enclosed in a sealed envelope marked on the outside lower right-hand corner indicating:

1. The bidder's name and address.
2. The project number.
3. The title of the project.
4. The time and date the bids are to be received.

(c) It is the sole responsibility of the bidder to see that his bid is received in proper time. Any bids received after the scheduled closing time for receipt of bids will be returned to the bidder unopened.

(d) The signatures of all persons shall be in longhand. Any interlineations, alterations, or erasures must be initialed by the signer of the bid.

(e) Bids shall not contain any recapitulations of the work to be done. No oral, telegraphic, telephonic, or modified proposals will be considered.

3. BID SECURITY: Each proposal shall be accompanied by a proposal guarantee in the form of a certified or cashier's check or bid bond, with a properly executed Power of Attorney attached, in an amount equal at least to ten percent (10%) of the proposal payable without condition to the City. If a bid bond is submitted with the bid it shall be issued by a company licensed with the Arizona Department of Insurance and authorized to issue such bonds in this state. **NO BONDS ISSUED BY INDIVIDUAL SURETIES WILL BE ACCEPTED. The company issuing the bid bond shall have a rating of not less than A- in the BEST rating available at the time this project was let to bid.** The proposal guarantee shall guarantee that the bidder, if awarded the contract, will, within ten (10) working days after the award, execute such contract in accordance with the proposal and in manner and form required by the contract documents, and will furnish good and sufficient bond for the faithful performance of the same, a payment bond and a certificate of insurance. The bid securities of the three (3) lowest bidders will be retained until the contract is awarded, or other disposition made thereof. The bid securities of all bidders, except the three (3) lowest, will be returned promptly after the canvass of bids. In the event the Contractor fails, within ten (10) working days after the award, to execute said Contract and deliver the Performance and Labor and

Material Payment Bonds and the Certificate of Insurance, the Bid Security shall become the property of the City.

4. **WITHDRAWAL OF BID:** Any bidder may withdraw his bid, either personally, by telegram or by written request, at any time prior to the scheduled closing time for receipt of bids. No bid may be withdrawn by telephone. Any bid withdrawn will not be opened and will be returned to the bidder. After opening and reading of the bids, no bidder may withdraw his bid for a period of fifty (50) days from the date of opening and reading.

5. **LATE BIDS:** Bids received after the scheduled closing time for receipt of bids, as contained in the "Notice to Contractors," will not be considered and will be returned to the bidder.

6. **AWARD OR REJECTION OF BIDS:** The contract will be awarded to the lowest and best qualified responsive bidder complying with these instructions and with the "NOTICE TO CONTRACTORS." The City of Glendale, Arizona, however, reserves the right to accept or reject any or all bids or to waive any or all informalities or irregularities in the bid. Alternates may be accepted depending upon the availability of City funds. Accepted alternates will be considered in determining the lowest responsive and responsible bidder.

7. **BIDDERS INTERESTED IN MORE THAN ONE BID:** No person, firm or corporation shall be allowed to make, file, or be interested in more than one (1) bid for the same work unless alternate bids are called for in the specifications or any addenda. A person, firm, or corporation who has submitted a sub-proposal to a bidder, or who has quoted prices on materials to a bidder is not thereby disqualified from submitting a sub-proposal or quoting prices to other bidders.

8. **CONTRACT AND BONDS:** The form of contract, which the successful bidder as Contractor will be required to execute and the forms of bonds which he shall be required to furnish are included in the contract documents and should be carefully examined by the bidder. The successful bidder shall use the forms provided or such other forms as are acceptable by the City. The Contract and Performance and Labor and Material Payment Bonds will be executed in three (3) original counterparts. All bonds shall be issued by companies licensed with the Arizona Department of Insurance and authorized to issue such bonds in this state. **NO BONDS ISSUED BY INDIVIDUAL SURETIES WILL BE ACCEPTED.** The company issuing any bond shall have a rating of not less than A- in the BEST rating available at the time this project was let to bid.

9. **INSURANCE REQUIREMENTS:** Contractor, and each Sub-contractor performing work or providing materials related to this Agreement must procure and maintain the insurance coverages described (collectively, "Contractor's Policies"), until each Parties' obligations under this Agreement are completed. Contractor must at all times relevant hereto carry a commercial general liability policy with a combined single limit of at least \$1,000,000 per occurrence and \$2,000,000 annual aggregate. **Contracts in excess of \$250,000 shall require \$2,000,000 single occurrence/\$5,000,000 annual aggregate.**

Sub-contractors must at all times relevant hereto carry a general commercial liability policy with a combined single limit of at least \$1,000,000 per occurrence.

This commercial general liability insurance must include independent contractors' liability, contractual liability, broad form property coverage, products and completed operations, XCU hazards if requested by the City, and a separation of insurance provision.

These limits may be met through a combination of primary and excess liability coverage.

Auto. A business auto policy providing a liability limit of at least \$1,000,000 per accident for Contractor and \$1,000,000 per accident for Sub-contractors and covering owned, non-owned and hired automobiles.

Workers' Compensation and Employer's Liability. A workers' compensation and employer's liability policy providing at least the minimum benefits required by Arizona law.

Equipment Insurance. Contractor must secure, pay for, and maintain all-risk insurance as necessary to protect the City against loss of owned, non-owned, rented or leased capital equipment and tools, equipment and scaffolding, staging, towers and forms owned or rented by Contractor or its Sub-contractors.

10. **SUBCONTRACTORS LISTING AND CERTIFICATION OF CONTRACT COMPLIANCE:** The contractor will be required to furnish the form of subcontractors listing and certification of contract compliance with the executed contract documents. This information is requested for tracking and insurance purposes only.

11. **INTERPRETATION OF PLANS AND DOCUMENTS:** If any person contemplating a bid for proposed contract is in doubt as to the true meaning of any part of the plans, specifications, or other proposed contract documents, or finds discrepancies in or omissions from the plans and specifications, he may submit to the Engineering Department, a written request for an interpretation or correction thereof. The person submitting the request will be responsible for its prompt delivery. Questions received less than ninety-six (96) hours before the bid opening time may not be answered. Any interpretation or correction of the documents will be made only by Addendum, duly issued and a copy of such Addendum will be mailed or delivered to each person receiving a set of such documents. The City of Glendale will not be responsible for any other explanations or interpretations of the proposed documents.

12. **CHANGES TO PLANS AND DOCUMENTS:** Any changes to the plans and documents shall be made only by Addendum. No verbal or other changes to the plans and documents will be valid. A copy of each Addendum will be mailed or delivered as provided in Section 13 below.

13. **ADDENDUM:** Any addenda will be faxed, mailed or delivered to all who are known by the City to have received a complete set of bid documents, and to offices where bid documents have been filed for review purposes. It is the responsibility of each bidder to ascertain that he has received all addenda issued by telephoning the office identified in the NOTICE TO CONTRACTORS as the location where bid documents are available prior to submitting his bid.

Bidders shall acknowledge all addenda in the appropriate location on the "PROPOSAL" form. Failure to acknowledge receipt of Addenda shall render the bid proposal non-responsive and it will be rejected.

14. **ASSIGNMENT OF CONTRACT:** No assignment by the Contractor of any contract to be entered into hereunder, or any part thereof, or of funds to be received thereunder by the Contractor, will be recognized by the Owner by the Owner unless such assignment has had prior approval of the Owner, and the Surety has been given due notice of such assignment in writing and has consented thereto in writing.

15. PLANS AND SPECIFICATIONS TO SUCCESSFUL BIDDER: The successful bidder may obtain five (5) sets of plans and specifications for this project from the City.

16. TIME OF COMPLETION: The Contractor shall commence work under this project on or before the tenth day following receipt of the Notice to Proceed for that project from the City of Glendale and shall fully complete all work under the project within SEVENTY-FIVE (75) consecutive calendar days from and including the date of receipt of such Notice to Proceed. Time is of the essence in the completion of all work required under this contract. The Contractor shall, at all times, during the continuance of the contract, prosecute the work with such force and equipment as is sufficient to complete all work within the time specified.

17. CITY OF GLENDALE TRANSACTION PRIVILEGE TAX: The City of Glendale transaction privilege tax shall **NOT** be waived under the provisions of this contract. The current privilege tax rate can be obtained from the City of Glendale Sales Tax and Licenses Department. The Contractor shall be responsible for reporting and payment of all city, county, state or federal taxes.

18. PRE-BID CONFERENCE: A pre-bid conference will be held on APRIL 23, at 10:00 AM, in the Engineering Department Conference Room, 5850 West Glendale Avenue, Glendale, Arizona. Bidders, contractors, and other interested parties are invited to attend this conference which will be conducted by the Owner and Engineer to answer any questions.

19. ALTERNATES: Alternate proposals will not be considered unless called for in the documents or any addenda thereto. When alternates are requested, all requested alternates or alternate bid items, unless otherwise stated, shall be bid. If no change in the base bid will occur with the alternate, enter "No Change."

20. APPROVAL OF SUBSTITUTIONS: The materials, products and equipment described in the Documents and Addenda establish a standard or required function, dimension, appearance and quality to be met by any proposed substitution. No substitute will be considered, before bid opening, unless written request for approval has been received by the City Engineer at least ten (10) working days prior to the scheduled closing time for receipt of bids. Each such request shall include the name of the material or equipment for which it is to be substituted and a complete description of the proposed substitute including any drawings, cuts, performance and test data and any other information necessary for evaluation of the substitute. Bidder shall not be entitled to approval of a substitute.

If a substitute is approved, the approval shall be set forth in an Addendum. Bidders shall not rely upon approvals made in any other manner.

21. USE OF "EQUALS": When the specifications for materials, articles, products and equipment state "or equal," contractor may bid upon, and use materials, articles, products and equipment which will perform equally the duties imposed by the general design. The City Engineering Department will have the final approval of all materials, articles, products and equipment proposed to be used as an "equal." It shall not be purchased or installed without the prior written approval from the City Engineering Department.

Approvals for "equals," before bid opening, may be requested in writing to the City Engineering Department for approval. Requests must be received at least ten (10) days prior to the date set for opening the Bid Proposals. The request shall state the name of the material, article, product or

equipment for which the item is sought to be considered an equal and a complete description of the proposed equal including any drawings, cuts, performance and test data and any other information necessary for approval of the equal. All approvals will be issued in the form of an addendum.

22. EXAMINATION OF CONTRACT DOCUMENTS AND VISIT SITE: Before submitting a Bid Proposal, bidders should carefully examine the Contract Documents, visit the site of the work, fully inform themselves as to all existing conditions and limitations. No consideration will be granted for any alleged misunderstanding of the material, articles or piece of equipment to be furnished or work to be done. It is understood that the tender of the Bid Proposal carries with it the agreement to all items and conditions referred to herein or indicated in the Contract Documents.

23. BIDDERS IN DEFAULT: No bid will be awarded to any person, firm or corporation that is not authorized by the Arizona Corporation Commission to do business in the State of Arizona, in arrears or is in default to the City of Glendale upon any debt or contract, or that is a defaulter as surety or otherwise upon any obligation to the City of Glendale, or has failed to faithfully perform any previous contract with the City of Glendale.

END OF INFORMATION FOR BIDDERS

PROPOSAL

Place City of Glendale

Date 4-30-15

Proposal of S. Banicki Construction, Inc. a Corporation organized and existing under the laws of the State of Arizona. a partnership consisting of _____; or an individual trading as _____.

TO THE HONORABLE MAYOR AND COUNCIL
CITY OF GLENDALE
GLENDALE, ARIZONA

Gentlemen:

The undersigned hereby proposes and agrees to furnish any and all required labor, materials, construction equipment, transportation and services for the construction of: **PROJECT 131423 - 2014/2015 BRIDGE MAINTENANCE REPAIR - VARIOUS LOCATIONS**, in strict conformity with the plans and specifications for the following unit prices:

(Extension of these unit prices on the basis of estimated quantities and the totaling of these extensions are for the purpose of comparing bids only. The mathematics of such extensions and totaling will be checked and corrected by the Engineering Department, before evaluating the bids, and the lowest of such corrected and checked totals will determine the lowest bids.)

PROJECT NO. 131423
2014/2015 Bridge Maintenance Repair - Various Locations
BID SCHEDULE (rev.)

ITEM	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL BID
1	Mobilization / Demobilization (ALL SITES)	1	LS	13,000 ⁰⁰	13,000 ⁰⁰
2	Traffic Control (ALL SITES)	1	LS	43,000 ⁰⁰	43,000 ⁰⁰
21	Owners Allowance for Construction Contingencies	1	LS	\$30,000.00	\$30,000.00
<i>Structure No. 9301</i>					
3	Partial Bridge Removal (Overhang)	1	LS	84,586 ⁰⁰	84,586 ⁰⁰
4	Structural Concrete (Class S - 4500psi)	87	CY	1,500 ⁰⁰	130,500 ⁰⁰
5	Replace Low Clearance Signs	2	EA	3,000 ⁰⁰	6,000 ⁰⁰
6	Reinforcing Steel	29,600	LB	120	35,520 ⁰⁰
22	Asbestos bearing pad removal (handling / proper disposal)	1	LS	4,500 ⁰⁰	4,500 ⁰⁰
<i>Structure No. 9443</i>					
7	Barrier and Sidewalk Removal	1	LS	15,000 ⁰⁰	15,000 ⁰⁰
8	Structural Concrete (Class AA - 4000psi)	7	CY	1,250 ⁰⁰	8,750 ⁰⁰
9	Reinforcing Steel	1,100	LB	125	1,375 ⁰⁰
<i>Structure No. 9885</i>					
10	Replace Missing Pedestrian Rail	1	LS	1,500 ⁰⁰	1,500 ⁰⁰
11	Replace Missing/Damaged Pedestrian Rail Pickets (10)	10	EA	450 ⁰⁰	4,500 ⁰⁰
12	Clean Clogged Bridge Deck Drains	1	LS	370 ⁰⁰	370 ⁰⁰
13	Secure Object Marker (SE Corner)	1	EA	300 ⁰⁰	300 ⁰⁰
<i>Structure No. 9886</i>					
14	Partial Barrier Removal	1	LS	5,700 ⁰⁰	5,700 ⁰⁰
15	Salvage and Reinstall Light Pole	1	LS	3,700 ⁰⁰	3,700 ⁰⁰
16	Replace Missing Top Rail	320	LF	13 ⁰⁰	4,160 ⁰⁰
17	Structural Concrete (Class AA - 4000psi)	2	CY	2,000 ⁰⁰	4,000 ⁰⁰
18	Reinforcing Steel	105	LB	1 ⁰⁰	105 ⁰⁰
19	Clean Clogged Bridge Deck Drains	1	LS	500 ⁰⁰	500 ⁰⁰
20	Erosion Remediation	15	CY	175 ⁰⁰	2,625 ⁰⁰
TOTAL BASE BID					399,091⁰⁰

PROJECT No. 131423 - 2014/2015 BRIDGE MAINTENANCE REPAIR - BID ALTERNATE NO. 1

ITEM	DESCRIPTION	QTY	UNIT	UNIT COST	TOTAL BID
BA1	Mobilization / Demobilization	1	LS	2,600 ⁰⁰	2,600 ⁰⁰
BA2	Traffic Control	1	LS	9,500 ⁰⁰	9,500 ⁰⁰
BA3	Partial approach slab surface removal / preparation / replacement (per specifications)	212	SF	140 ⁰⁰	29,680 ⁰⁰
BA4	Approach slab(s) Epoxy Healer / Sealer (per specifications)	2,040	SF	560	11,424 ⁰⁰
BA5	Owners Allowance for Construction Contingencies	1	LS	\$5,000.00	\$5,000.00
TOTAL BID ALTERNATE NO. 1					58,204⁰⁰

The undersigned hereby declares that he has visited the site(s) and has carefully examined the contract documents relating to the work covered by the above bid or bids.

Upon receipt of notice of the acceptance of this bid, we will execute the formal contract attached within ten (10) days, and will deliver a one hundred percent (100%) Performance Bond for the faithful performance of this Contract, together with a one hundred percent (100%) Payment Bond and Certificate of Insurance.

The bid security attached, with endorsement, in the sum of ten percent (10%) of the total bid, is to become the property of the City of Glendale, Arizona, in the event the Contract and Bonds are not executed within the time set forth, as liquidated damages for the delay and additional work caused thereby.

The undersigned has checked carefully all the above figures and understands that the City of Glendale, Arizona, will not be responsible for any errors or omissions on the part of the undersigned in making up this bid.

The undersigned understands that the Mayor and Council of the City of Glendale, Arizona, reserves the right to reject any or all bids or to waive any informalities or irregularities in the bid.

Respectfully submitted,

Arizona Contractor's
Classification and
License No.
CLASS A
ROC 091410

J. Benicki Construction, Inc.
Contractor

By 
Mike Abraham

6423 S. Ash Avenue


Tempe, AZ 85283
(Complete business address)

Telephone Number: 480-921-8016
Fax Number 480-921-9456

Bidder shall signify receipt of all Addenda here (if any):

Addenda (1) Dated 4-23-15

Failure to acknowledge receipt of all Addenda shall render the bid proposal non-responsive and will be rejected.

Acknowledged by 
Mike Abraham

CONSTRUCTION AGREEMENT

This Construction Agreement ("Agreement") is entered into and effective between the CITY OF GLENDALE, an Arizona municipal corporation ("City"), and J. Banicki Construction, Inc., an Arizona corporation ("Contractor") as of the 9th day of June, 2015.

RECITALS

- A. City intends to undertake a project for the benefit of the public and with public funds that is more fully set forth in the **Notice to Contractors** and the attached **Exhibit A** ("Project");
- B. City desires to retain the services of Contractor to perform those specific duties and produce the specific work as set forth in the Project, the plans and specifications, the **Information for Bidders**, and the **Maricopa Association of Governments** ("MAG") **General and Supplemental Conditions and Provisions**;
- C. City and Contractor desire to memorialize their agreement with this document.

AGREEMENT

In consideration of the Recitals, which are confirmed as true and correct and incorporated by this reference, the mutual promises and covenants contained in this Agreement, and other good and valuable consideration, City and Contractor agree as follows:

1. Project.

1.1 Scope. Contractor will provide all services and material necessary to assure the Project is completed timely and efficiently consistent with Project requirements, including, but not limited to, working in close interaction and interfacing with City and its designated employees, and working closely with others, including other contractors, providers or consultants retained by City.

1.2 Documents. The following documents are, by this reference, entirely incorporated into this Agreement and attached Exhibits as though fully set forth herein:

- (A) Notice to Contractors;
- (B) Information for Bidders;
- (C) MAG General Conditions, Supplemental General Conditions, Special and Technical Provisions;
- (D) Proposal;
- (E) Bid Bond;
- (F) Payment Bond;
- (G) Performance Bond;
- (H) Certificate of Insurance;
- (I) Appendix; and
- (J) Plans and Addenda thereto.

Should a conflict exist between this Agreement (and its attachments), and any of the incorporated documents as listed above, the provisions of this Agreement shall govern.

1.3 Project Team.

(A) Project Manager. Contractor will designate an employee as Project Manager with sufficient training, knowledge, and experience to, in the City's opinion, to complete the project and handle all aspects of the Project such that the work produced by Contractor is consistent with applicable standards as detailed in this Agreement.

(B) Project Team.

- (1) The Project manager and all other employees assigned to the project by Contractor will comprise the "Project Team."
- (2) Project Manager will have responsibility for and will supervise all other employees assigned to the project by Contractor.

Project 131423

(C) Sub-contractors.

- (1) Contractor may engage specific technical contractor (each a "Sub-contractor") to furnish certain service functions.
- (2) Contractor will remain fully responsible for Sub-contractor's services.
- (3) Sub-contractors must be approved by the City, unless the Sub-contractor was previously mentioned in the response to the solicitation.
- (4) Contractor shall certify by letter that contracts with Sub-contractors have been executed incorporating requirements and standards as set forth in this Agreement.

2. **Schedule.** The Project will be undertaken in a manner that ensures it is completed in a timely and efficient manner. If not otherwise stated in **Exhibit A**, the Project shall be completed by no later than within seventy five (75) consecutive calendar days from and including the date of receipt of the Notice to Proceed.

3. **Contractor's Work.**

3.1 **Standard.** Contractor must perform services in accordance with the standards of due diligence, care, and quality prevailing among contractors having substantial experience with the successful furnishing of services and materials for projects that are equivalent in size, scope, quality, and other criteria under the Project and identified in this Agreement.

3.2 **Licensing.** Contractor warrants that:

- (A) Contractor and Sub-contractors will hold all appropriate and required licenses, registrations and other approvals necessary for the lawful furnishing of services ("Approvals"); and
- (B) Neither Contractor nor any Sub-contractor has been debarred or otherwise legally excluded from contracting with any federal, state, or local governmental entity ("Debarment").
 - (1) City is under no obligation to ascertain or confirm the existence or issuance of any Approvals or Debarments or to examine Contractor's contracting ability.
 - (2) Contractor must notify City immediately if any Approvals or Debarment changes during the Agreement's duration and the failure of the Contractor to notify City as required will constitute a material default of this Agreement.

3.3 **Compliance.** Services and materials will be furnished in compliance with applicable federal, state, county and local statutes, rules, regulations, ordinances, building codes, life safety codes, or other standards and criteria designated by City.

3.4 **Coordination; Interaction.**

- (A) If the City determines that the Project requires the coordination of professional services or other providers, Contractor will work in close consultation with City to proactively interact with any other contractors retained by City on the Project ("Coordinating Entities").
- (B) Subject to any limitations expressly stated in the budget, Contractor will meet to review the Project, schedules, budget, and in-progress work with Coordinating Entities and the City as often and for durations as City reasonably considers necessary in order to ensure the timely work delivery and Project completion.
- (C) If the Project does not involve Coordinating Entities, Contractor will proactively interact with any other contractors when directed by City to obtain or disseminate timely information for the proper execution of the Project.

3.5 **Hazardous Substances.** Contractor is responsible for the appropriate handling, disposal of, and if necessary, any remediation and all losses and damages to the City, associated with the use or release of hazardous substances by Contractor in connection with completion of the Project.

Project 131423

3.6 **Warranties.** At any time within two years after completion of the Project, Contractor must, at Contractor's sole expense and within 20 days of written notice from the City, uncover, correct and remedy all defects in Contractor's work. City will accept a manufacturer's warranty on approved equipment as satisfaction of the Contractor's warranty under this subsection.

3.7. **Bonds.** Upon execution of this Agreement, and if applicable, Contractor must furnish Payment and Performance bonds as required under A.R.S. § 34-608.

4. **Compensation for the Project.**

4.1 **Compensation.** Contractor's compensation for the Project, including those furnished by its Sub-contractors will not exceed \$457,295, as specifically detailed in the Contractor's bid and set forth in **Exhibit B** ("Compensation").

4.2 **Change in Scope of Project.** The Compensation may be equitably adjusted if the originally contemplated scope of services as outlined in the Project is significantly modified by the City.

(A) Adjustments to the Scope or Compensation require a written amendment to this Agreement and may require City Council approval.

(B) Additional services which are outside the scope of the Project and not contained in this Agreement may not be performed by the Contractor without prior written authorization from the City.

5. **Billings and Payment.**

5.1 **Applications.**

(A) The Contractor will submit monthly invoices (each, a "Payment Application") to City's Project Manager and City will remit payments based upon the Payment Application as stated below.

(B) The period covered by each Payment Application will be one calendar month ending on the last day of the month.

5.2 **Payment.**

(A) After a full and complete Payment Application is received, City will process and remit payment within 30 days.

(B) Payment may be subject to or conditioned upon City's receipt of:

(1) Completed work generated by Contractor and its Sub-contractors; and

(2) Unconditional waivers and releases on final payment from Sub-contractors as City may reasonably request to assure the Project will be free of claims arising from required performances under this Agreement.

5.3 **Review and Withholding.** City's Project Manager will timely review and certify Payment Applications.

(A) If the Payment Application is rejected, the Project Manager will issue a written listing of the items not approved for payment.

(B) City may withhold an amount sufficient to pay expenses that City reasonably expects to incur in correcting the deficiency or deficiencies rejected for payment.

(C) Contractor will provide, by separate cover, and concurrent with the execution of this Agreement, all required financial information to the City, including City of Glendale Transaction Privilege License and Federal Taxpayer identification numbers.

(D) City will temporarily withhold Compensation amounts as required by A.R.S. 34-221(C).

6. **Termination.**

6.1 **For Convenience.** City may terminate this Agreement for convenience, without cause, by delivering a written termination notice stating the effective termination date, which may not be less than 15 days following the date of delivery.

- (A) Contractor will be equitably compensated any services and materials furnished prior to receipt of the termination notice and for reasonable costs incurred.
- (B) Contractor will also be similarly compensated for any approved effort expended and approved costs incurred that are directly associated with Project closeout and delivery of the required items to the City.

6.2 **For Cause.** City may terminate this Agreement for cause if Contractor fails to cure any breach of this Agreement within seven days after receipt of written notice specifying the breach.

- (A) Contractor will not be entitled to further payment until after City has determined its damages. If City's damages resulting from the breach, as determined by City, are less than the equitable amount due but not paid Contractor for Service and Repair furnished, City will pay the amount due to Contractor, less City's damages.
- (B) If City's direct damages exceed amounts otherwise due to Contractor, Contractor must pay the difference to City immediately upon demand; however, Contractor will not be subject to consequential damages more than \$1,000,000 or the amount of this Agreement, whichever is greater.

7. **Insurance.**

7.1 **Requirements.** Contractor must obtain and maintain the following insurance ("Required Insurance"):

- (A) Contractor and Sub-contractors. Contractor, and each Sub-contractor performing work or providing materials related to this Agreement must procure and maintain the insurance coverages described below (collectively, "Contractor's Policies"), until each Parties' obligations under this Agreement are completed.
- (B) General Liability.
 - (1) Contractor must at all times relevant hereto carry a commercial general liability policy with a combined single limit of at least \$1,000,000 per occurrence and \$2,000,000 annual aggregate.
 - (2) Sub-contractors must at all times relevant hereto carry a general commercial liability policy with a combined single limit of at least \$1,000,000 per occurrence.
 - (3) This commercial general liability insurance must include independent contractors' liability, contractual liability, broad form property coverage, products and completed operations, XCU hazards if requested by the City, and a separation of insurance provision.
 - (4) These limits may be met through a combination of primary and excess liability coverage.
- (C) Auto. A business auto policy providing a liability limit of at least \$1,000,000 per accident for Contractor and 1,000,000 per accident for Sub-contractors and covering owned, non-owned and hired automobiles.
- (D) Workers' Compensation and Employer's Liability. A workers' compensation and employer's liability policy providing at least the minimum benefits required by Arizona law.
- (E) Equipment Insurance. Contractor must secure, pay for, and maintain all-risk insurance as necessary to protect the City against loss of owned, non-owned, rented or leased capital equipment and tools, equipment and scaffolding, staging, towers and forms owned or rented by Contractor or its Sub-contractors.

- (F) Notice of Changes. Contractor's Policies must provide for not less than 30 days' advance written notice to City Representative of:
- (1) Cancellation or termination of Contractor or Sub-contractor's Policies;
 - (2) Reduction of the coverage limits of any of Contractor or and Sub-contractor's Policies; and
 - (3) Any other material modification of Contractor or Sub-contractor's Policies related to this Agreement.
- (G) Certificates of Insurance.
- (1) Within 10 business days after the execution of the Agreement, Contractor must deliver to City Representative certificates of insurance for each of Contractor and Sub-contractor's Policies, which will confirm the existence or issuance of Contractor and Sub-contractor's Policies in accordance with the provisions of this section, and copies of the endorsements of Contractor and Sub-contractor's Policies in accordance with the provisions of this section.
 - (2) City is and will be under no obligation either to ascertain or confirm the existence or issuance of Contractor and Sub-contractor's Policies, or to examine Contractor and Sub-contractor's Policies, or to inform Contractor or Sub-contractor in the event that any coverage does not comply with the requirements of this section.
 - (3) Contractor's failure to secure and maintain Contractor Policies and to assure Sub-contractor policies as required will constitute a material default under this Agreement.
- (H) Other Contractors or Vendors.
- (1) Other contractors or vendors that may be contracted by Contractor with in connection with the Project must procure and maintain insurance coverage as is appropriate to their particular agreement.
 - (2) This insurance coverage must comply with the requirements set forth above for Contractor's Policies (e.g., the requirements pertaining to endorsements to name the parties as additional insured parties and certificates of insurance).
- (I) Policies. Except with respect to workers' compensation and employer's liability coverages, the City must be named and properly endorsed as additional insureds on all liability policies required by this section.
- (1) The coverage extended to additional insureds must be primary and must not contribute with any insurance or self insurance policies or programs maintained by the additional insureds.
 - (2) All insurance policies obtained pursuant to this section must be with companies legally authorized to do business in the State of Arizona and acceptable to all parties.

7.2 Sub-contractors.

- (A) Contractor must also cause its Sub-contractors to obtain and maintain the Required Insurance.
- (B) City may consider waiving these insurance requirements for a specific Sub-contractor if City is satisfied the amounts required are not commercially available to the Sub-contractor and the insurance the Sub-contractor does have is appropriate for the Sub-contractor's work under this Agreement.
- (C) Contractor and Sub-contractors must provide to the City proof of Required Insurance whenever requested.

7.3 Indemnification.

- (A) To the fullest extent permitted by law, Contractor must defend, indemnify, and hold harmless City and its elected officials, officers, employees and agents (each, an "Indemnified Party," collectively, the

"Indemnified Parties"), for, from, and against any and all claims, demands, actions, damages, judgments, settlements, personal injury (including sickness, disease, death, and bodily harm), property damage (including loss of use), infringement, governmental action and all other losses and expenses, including attorneys' fees and litigation expenses (each, a "Demand or Expense"; collectively, "Demands or Expenses") asserted by a third-party (i.e. a person or entity other than City or Contractor) and that arises out of or results from the breach of this Agreement by the Contractor or the Contractor's negligent actions, errors or omissions (including any Sub-contractor or other person or firm employed by Contractor), whether sustained before or after completion of the Project.

- (B) This indemnity and hold harmless policy applies even if a Demand or Expense is in part due to the Indemnified Party's negligence or breach of a responsibility under this Agreement, but in that event, Contractor shall be liable only to the extent the Demand or Expense results from the negligence or breach of a responsibility of Contractor or of any person or entity for whom Contractor is responsible.
- (C) Contractor is not required to indemnify any Indemnified Parties for, from, or against any Demand or Expense resulting from the Indemnified Party's sole negligence or other fault solely attributable to the Indemnified Party.

7.4 Waiver of Subrogation. Contractor waives, and will require any Subcontractor to waive, all rights of subrogation against the City to the extent of all losses or damages covered by any policy of insurance.

8. Immigration Law Compliance.

- 8.1 Contractor, and on behalf any subcontractor, warrants, to the extent applicable under A.R.S. § 41-4401, compliance with all federal immigration laws and regulations that relate to their employees as well as compliance with A.R.S. § 23-214(A) which requires registration and participation with the E-Verify Program.
- 8.2 Any breach of warranty under subsection 8.1 above is considered a material breach of this Agreement and is subject to penalties up to and including termination of this Agreement.
- 8.3 City retains the legal right to inspect the papers of any Contractor or subcontractor employee who performs work under this Agreement to ensure that the Contractor or any subcontractor is compliant with the warranty under subsection 8.1 above.
- 8.4 City may conduct random inspections, and upon request of City, Contractor shall provide copies of papers and records of Contractor demonstrating continued compliance with the warranty under subsection 8.1 above. Contractor agrees to keep papers and records available for inspection by the City during normal business hours and will cooperate with City in exercise of its statutory duties and not deny access to its business premises or applicable papers or records for the purposes of enforcement of this section 8.
- 8.5 Contractor agrees to incorporate into any subcontracts under this Agreement the same obligations imposed upon Contractor and expressly accrue those obligations directly to the benefit of the City. Contractor also agrees to require any subcontractor to incorporate into each of its own subcontracts under this Agreement the same obligations above and expressly accrue those obligations to the benefit of the City.
- 8.6 Contractor's warranty and obligations under this section to the City is continuing throughout the term of this Agreement or until such time as the City determines, in its sole discretion, that Arizona law has been modified in that compliance with this section is no longer a requirement.
- 8.7 The "E-Verify Program" above means the employment verification program administered by the United States Department of Homeland Security, the Social Security Administration, or any successor program.

9. Conflict. Contractor acknowledges this Agreement is subject to A.R.S. § 38-511, which allows for cancellation of this Agreement in the event any person who is significantly involved in initiating, negotiating, securing, drafting, or creating the Agreement on City's behalf is also an employee, agent, or consultant of any other party to this Agreement.

10. Non-Discrimination Policies. Contractor must not discriminate against any employee or applicant for employment on the basis of race, religion, color sex or national origin. Contractor must develop, implement and maintain non-discrimination policies and post the policies in conspicuous places visible to employees and applicants for employment. Contractor will require any Sub-contractor to be bound to the same requirements as stated within this section.

Project 131423

11. Notices.

11.1 A notice, request or other communication that is required or permitted under this Agreement (each a "Notice") will be effective only if:

- (A) The Notice is in writing, and
- (B) Delivered in person or by private express overnight delivery service (delivery charges prepaid), certified or registered mail (return receipt requested).
- (C) Notice will be deemed to have been delivered to the person to whom it is addressed as of the date of receipt, if:
 - (1) Received on a business day, or before 5:00 p.m., at the address for Notices identified for the Party in this Agreement by U.S. Mail, hand delivery, or overnight courier on or before 5:00 p.m.; or
 - (2) As of the next business day after receipt, if received after 5:00 p.m.
- (D) The burden of proof of the place and time of delivery is upon the Party giving the Notice.
- (E) Digitalized signatures and copies of signatures will have the same effect as original signatures.

11.2 Representatives.

(A) Contractor. Contractor's representative ("Contractor's Representative") authorized to act on Contractor's behalf with respect to the Project, and his or her address for Notice delivery is:

J. Banicki Construction, Inc.
Attn: Mike Abraham
6423 South Ash Avenue
Tempe, Arizona 85283

(B) City. City's representative ("City's Representative") authorized to act on City's behalf, and his or her address for Notice delivery is:

City of Glendale
Attn: Tom Kaczmarowski
5850 West Glendale Avenue
Glendale, Arizona 85301

With required copies to:

City of Glendale
City Manager
5850 West Glendale Avenue
Glendale, Arizona 85301

City of Glendale
City Attorney
5850 West Glendale Avenue
Glendale, Arizona 85301

(C) Concurrent Notices.

- (1) All notices to City's representative must be given concurrently to City Manager and City Attorney.
- (2) A notice will not be considered to have been received by City's representative until the time that it has also been received by City Manager and City Attorney.
- (3) City may appoint one or more designees for the purpose of receiving notice by delivery of a written notice to Contractor identifying the designee(s) and their respective addresses for notices.

(D) **Changes**. Contractor or City may change its representative or information on Notice, by giving Notice of the change in accordance with this section at least ten days prior to the change.

Project 131423

12. **Financing Assignment.** City may assign this Agreement to any City-affiliated entity, including a non-profit corporation or other entity whose primary purpose is to own or manage the Project.

13. **Entire Agreement; Survival; Counterparts; Signatures.**

13.1 **Integration.** This Agreement contains, except as stated below, the entire agreement between City and Contractor and supersedes all prior conversations and negotiations between the parties regarding the Project or this Agreement.

- (A) Neither Party has made any representations, warranties or agreements as to any matters concerning the Agreement's subject matter.
- (B) Representations, statements, conditions, or warranties not contained in this Agreement will not be binding on the parties.
- (C) Any solicitation, addendums and responses submitted by the Contractor are incorporated fully into this Agreement as Exhibit A. Any inconsistency between Exhibit A and this Agreement will be resolved by the terms and conditions stated in this Agreement.

13.2 **Interpretation.**

- (A) The parties fairly negotiated the Agreement's provisions to the extent they believed necessary and with the legal representation they deemed appropriate.
- (B) The parties are of equal bargaining position and this Agreement must be construed equally between the parties without consideration of which of the parties may have drafted this Agreement.
- (C) The Agreement will be interpreted in accordance with the laws of the State of Arizona.

13.3 **Survival.** Except as specifically provided otherwise in this Agreement each warranty, representation, indemnification and hold harmless provision, insurance requirement, and every other right, remedy and responsibility of a Party, will survive completion of the Project, or the earlier termination of this Agreement.

13.4 **Amendment.** No amendment to this Agreement will be binding unless in writing and executed by the parties. Any amendment may be subject to City Council approval.

13.5 **Remedies.** All rights and remedies provided in this Agreement are cumulative and the exercise of any one or more right or remedy will not affect any other rights or remedies under this Agreement or applicable law.

13.6 **Severability.** If any provision of this Agreement is voided or found unenforceable, that determination will not affect the validity of the other provisions, and the voided or unenforceable provision will be reformed to conform to applicable law.

13.7 **Counterparts.** This Agreement may be executed in counterparts, and all counterparts will together comprise one instrument.

14. **Dispute Resolution.** Each claim, controversy and dispute ("Dispute") between Contractor and City will be resolved in accordance with Exhibit C. The final determination will be made by the City.


15. **Exhibits.** The following exhibits, with reference to the term in which they are first referenced, are incorporated by this reference.

Exhibit A	Project
Exhibit B	Compensation
Exhibit C	Dispute Resolution

Project 131423

The parties enter into this Agreement as of the date shown above.

City of Glendale,
an Arizona municipal corporation



By: Richard A. Bowers
Its: Acting City Manager

ATTEST:


City Clerk

(SEAL)

APPROVED AS TO FORM:


City Attorney

J. Banicki Construction, Inc.
an Arizona corporation


By: Michael D. Abraham
Its: President

WOMEN-OWNED/MINORITY BUSINESS [] YES [] NO
CITY OF GLENDALE TRANSACTION PRIVILEGE TAX NO. _____
FEDERAL TAXPAYER IDENTIFICATION NO. _____

Project 131423

**EXHIBIT A
CONSTRUCTION AGREEMENT**

PROJECT

Project includes various repairs of approximately 6 transportation bridges at various locations. Repairs include, but are not limited to, removal/replacement of structural concrete/steel, repair of signage, guard/pedestrian rail repairs, traffic control and additional miscellaneous work.

Project 131423

**EXHIBIT B
CONSTRUCTION AGREEMENT**

COMPENSATION

METHOD AND AMOUNT OF COMPENSATION

By bid, including all services, materials and costs.

NOT-TO-EXCEED AMOUNT

The total amount of compensation paid to Contractor for full completion of all work required by the Project during the entire term of the Project must not exceed \$457,295.

DETAILED PROJECT COMPENSATION

Base Bid:	\$399,091.00
Alternate One:	\$ 58,204.00
Total Not To Exceed:	\$457,295.00

**EXHIBIT C
CONSTRUCTION AGREEMENT**

DISPUTE RESOLUTION

1. Disputes.

- 1.1 Commitment. The parties commit to resolving all disputes promptly, equitably, and in a good-faith, cost-effective manner.
- 1.2 Application. The provisions of this Exhibit will be used by the parties to resolve all controversies, claims, or disputes ("Dispute") arising out of or related to this Agreement-including Disputes regarding any alleged breaches of this Agreement.
- 1.3 Initiation. A party may initiate a Dispute by delivery of written notice of the Dispute, including the specifics of the Dispute, to the Representative of the other party as required in this Agreement.
- 1.4 Informal Resolution. When a Dispute notice is given, the parties will designate a member of their senior management who will be authorized to expeditiously resolve the Dispute.
- (A) The parties will provide each other with reasonable access during normal business hours to any and all non-privileged records, information and data pertaining to any Dispute in order to assist in resolving the Dispute as expeditiously and cost effectively as possible;
- (B) The parties' senior managers will meet within 10 business days to discuss and attempt to resolve the Dispute promptly, equitably, and in a good faith manner, and
- (C) The Senior Managers will agree to subsequent meetings if both parties agree that further meetings are necessary to reach a resolution of the Dispute.

2. Arbitration.

- 2.1 Rules. If the parties are unable to resolve the Dispute by negotiation within 30 days from the Dispute notice, and unless otherwise informal discussions are extended by the mutual agreement, the Dispute will be decided by binding arbitration in accordance with Construction Industry Rules of the AAA, as amended herein. Although the arbitration will be conducted in accordance with AAA Rules, it will not be administered by the AAA, but will be heard independently.
- (A) The parties will exercise best efforts to select an arbitrator within 5 business days after agreement for arbitration. If the parties have not agreed upon an arbitrator within this period, the parties will submit the selection of the arbitrator to one of the principals of the mediation firm of Scott & Skelly, LLC, who will then select the arbitrator. The parties will equally share the fees and costs incurred in the selection of the arbitrator.
- (B) The arbitrator selected must be an attorney with at least 15 years experience with commercial construction legal matters in Maricopa County, Arizona, be independent, impartial, and not have engaged in any business for or adverse to either Party for at least 10 years.
- 2.2 Discovery. The extent and the time set for discovery will be as determined by the arbitrator. Each Party must, however, within ten (10) days of selection of an arbitrator deliver to the other Party copies of all documents in the delivering party's possession that are relevant to the dispute.
- 2.3 Hearing. The arbitration hearing will be held within 90 days of the appointment of the arbitrator. The arbitration hearing, all proceedings, and all discovery will be conducted in Glendale, Arizona unless otherwise agreed by the parties or required as a result of witness location. Telephonic hearings and other reasonable arrangements may be used to minimize costs.
- 2.4 Award. At the arbitration hearing, each Party will submit its position to the arbitrator, evidence to support that position, and the exact award sought in this matter with specificity. The arbitrator must select the award sought

Project 131423

by one of the parties as the final judgment and may not independently alter or modify the awards sought by the parties, fashion any remedy, or make any equitable order. The arbitrator has no authority to consider or award punitive damages.

- 2.5 Final Decision. The Arbitrator's decision should be rendered within 15 days after the arbitration hearing is concluded. This decision will be final and binding on the Parties.
- 2.6 Costs. The prevailing party may enter the arbitration in any court having jurisdiction in order to convert it to a judgment. The non-prevailing party shall pay all of the prevailing party's arbitration costs and expenses, including reasonable attorney's fees and costs.

3. **Services to Continue Pending Dispute.** Unless otherwise agreed to in writing, Contractor must continue to perform and maintain progress of required services during any Dispute resolution or arbitration proceedings, and City will continue to make payment to Contractor in accordance with this Agreement.

4. **Exceptions.**

- 4.1 Third Party Claims. City and Contractor are not required to arbitrate any third-party claim, cross-claim, counter claim, or other claim or defense of a third-party who is not obligated by contract to arbitrate disputes with City and Contractor.
- 4.2 Liens. City or Contractor may commence and prosecute a civil action to contest a lien or stop notice, or enforce any lien or stop notice, but only to the extent the lien or stop notice the Party seeks to enforce is enforceable under Arizona Law, including, without limitation, an action under A.R.S. § 33-420, without the necessity of initiating or exhausting the procedures of this Exhibit.
- 4.3 Governmental Actions. This Exhibit does not apply to, and must not be construed to require arbitration of, any claims, actions or other process filed or issued by City of Glendale Building Safety Department or any other agency of City acting in its governmental permitting or other regulatory capacity.



THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

ADDITIONAL INSURED - OWNERS, LESSEES OR CONTRACTORS - OPTION I

This endorsement modifies insurance provided under the following:

COMMERCIAL GENERAL LIABILITY COVERAGE PART

SCHEDULE

Name Of Additional Insured Person(s) Or Organization(s):	Designated Project(s) Or Location(s) Of Covered Operations:
BLANKET WHEN REQUIRED BY WRITTEN CONTRACT	
Information required to complete this Schedule, if not shown above, will be shown in the Declarations.	

A. With respect to those person(s) or organization(s) shown in the Schedule above when you have agreed in a written contract or written agreement to provide insurance such as is afforded under this policy to them, Subparagraph f., **Any Other Party**, under the **Additional Insureds When Required By Written Contract, Written Agreement Or Permit Paragraph of Section II – Who Is An Insured** is replaced with the following:

f. Any Other Party

Any other person or organization who is not an insured under Paragraphs a. through e. above, but only with respect to liability for "bodily injury", "property damage" or "personal and advertising injury" caused, in whole or in part, by your acts or omissions or the acts or omissions of those acting on your behalf:

- (1) In the performance of your ongoing operations for such additional insured at the project(s) or location(s) designated in the Schedule;
- (2) In connection with your premises owned by or rented to you and shown in the Schedule; or

(3) In connection with "your work" for the additional insured at the project(s) or location(s) designated in the Schedule and included within the "products-completed operations hazard", but only if:

- (a) The written contract or written agreement requires you to provide such coverage to such additional insured at the project(s) or location(s) designated in the Schedule; and
- (b) This Coverage Part provides coverage for "bodily injury" or "property damage" included within the "products-completed operations hazard".

The insurance afforded to the additional insured shown in the Schedule applies:

- (1) Only if the "bodily injury" or "property damage" occurs, or the "personal and advertising injury" offense is committed:
 - (a) During the policy period; and
 - (b) Subsequent to the execution of such written contract or written agreement; and

WAIVER OF TRANSFER OF RIGHTS OF RECOVERY AGAINST OTHERS TO US

This endorsement modifies insurance provided under the following:

COMMERCIAL GENERAL LIABILITY COVERAGE PART
PRODUCTS/COMPLETED OPERATIONS LIABILITY COVERAGE PART

SCHEDULE

Name Of Person Or Organization:

BLANKET WHEN REQUIRED BY WRITTEN CONTRACT

Information required to complete this Schedule, if not shown above, will be shown in the Declarations.

The following is added to Paragraph 8. Transfer Of Rights Of Recovery Against Others To Us of Section IV – Conditions:

We waive any right of recovery we may have against the person or organization shown in the Schedule above because of payments we make for injury or damage arising out of your ongoing operations or "your work" done under a contract with that person or organization and included in the "products-completed operations hazard". This waiver applies only to the person or organization shown in the Schedule above.

THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

DESIGNATED INSURED FOR COVERED AUTOS LIABILITY COVERAGE

This endorsement modifies insurance provided under the following:

AUTO DEALERS COVERAGE FORM
BUSINESS AUTO COVERAGE FORM
MOTOR CARRIER COVERAGE FORM

With respect to coverage provided by this endorsement, the provisions of the Coverage Form apply unless modified by this endorsement.

This endorsement identifies person(s) or organization(s) who are "insureds" for Covered Autos Liability Coverage under the Who Is An Insured provision of the Coverage Form. This endorsement does not alter coverage provided in the Coverage Form.

This endorsement changes the policy effective on the inception date of the policy unless another date is indicated below.

Named Insured: STERLING CONSTRUCTION COMPANY, INC.

Endorsement Effective Date: 03/01/2015

SCHEDULE

Name Of Person(s) Or Organization(s):
BLANKET WHEN REQUIRED BY WRITTEN CONTRACT

Information required to complete this Schedule, if not shown above, will be shown in the Declarations.

Each person or organization shown in the Schedule is an "insured" for Covered Autos Liability Coverage, but only to the extent that person or organization qualifies as an "insured" under the Who Is An Insured provision contained in Paragraph A.1. of Section II – Covered Autos Liability Coverage in the Business Auto and Motor Carrier Coverage Forms and Paragraph D.2. of Section I – Covered Autos Coverages of the Auto Dealers Coverage Form.

POLICY NUMBER: 61 CSE QU2062



THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

**AMENDMENT OF THE DECLARATIONS - ADDITIONAL
PERSONS OR ORGANIZATIONS DESIGNATED AS NAMED
INSUREDS**

The following person(s) or organization(s) are added to the Declarations as Named Insureds:

STERLING CONSTRUCTION COMPANY, INC.
TEXAS STERLING CONSTRUCTION CO.
STERLING HOUSTON HOLDINGS, INC.
STERLING HAWAII ASPHALT, LLC
RHB PROPERTIES, LLC
ROAD AND HIGHWAY BUILDERS, LLC
ROAD AND HIGHWAY BUILDERS, INC.
ROAD AND HIGHWAY BUILDERS OF CALIFORNIA, INC.
RALPH L. WADSWORTH CONSTRUCTION COMPANY, LLC
RALPH L. WADSWORTH CONSTRUCTION CO. LP
J. BANICKI CONSTRUCTION, INC.
MYERS & SONS CONSTRUCTION, LP
C & J MYERS, INC.
RDI FOUNDATION DRILLING
STERLING CONSTRUCTION COMPANY, INC. DBA STERLING DELAWARE
HOLDING COMPANY, INC.
MYERS AND SONS / ACC JV

THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

COMMERCIAL AUTOMOBILE BROAD FORM ENDORSEMENT

This endorsement modifies insurance provided under the following:

BUSINESS AUTO COVERAGE FORM

To the extent that the provisions of this endorsement provide broader benefits to the "insured" than other provisions of the Coverage Form, the provisions of this endorsement apply.

1. BROAD FORM INSURED

A. Subsidiaries and Newly Acquired or Formed Organizations

The Named Insured shown in the Declarations is amended to include:

- (1) Any legal business entity other than a partnership or joint venture, formed as a subsidiary in which you have an ownership interest of more than 50% on the effective date of the Coverage Form. However, the Named Insured does not include any subsidiary that is an "insured" under any other automobile policy or would be an "insured" under such a policy but for its termination or the exhaustion of its Limit of Insurance.
- (2) Any organization that is acquired or formed by you and over which you maintain majority ownership. However, the Named Insured does not include any newly formed or acquired organization:
 - (a) That is a partnership or joint venture,
 - (b) That is an "insured" under any other policy,
 - (c) That has exhausted its Limit of Insurance under any other policy, or
 - (d) 180 days or more after its acquisition or formation by you, unless you have given us notice of the acquisition or formation.

Coverage does not apply to "bodily injury" or "property damage" that results from an "accident" that occurred before you formed or acquired the organization.

B. Employees as Insureds

Paragraph A.1. - WHO IS AN INSURED - of SECTION II - LIABILITY COVERAGE is amended to add:

- d. Any "employee" of yours while using a covered "auto" you don't own, hire or borrow in your business or your personal affairs.

C. Lessors as Insureds

Paragraph A.1. - WHO IS AN INSURED - of Section II - Liability Coverage is amended to add:

- e. The lessor of a covered "auto" while the "auto" is leased to you under a written agreement if:
 - (1) The agreement requires you to provide direct primary insurance for the lessor and
 - (2) The "auto" is leased without a driver.

Such a leased "auto" will be considered a covered "auto" you own and not a covered "auto" you hire.

D. Additional Insured If Required by Contract

- (1) Paragraph A.1. - WHO IS AN INSURED - of Section II - Liability Coverage is amended to add:
 - f. When you have agreed, in a written contract or written agreement, that a person or organization be added as an additional insured on your business auto policy, such person or organization is an "insured", but only to the extent such person or organization is liable for "bodily injury" or "property damage" caused by the conduct of an "insured" under paragraphs a. or b. of Who Is An Insured with regard to the ownership, maintenance or use of a covered "auto."

If an "employee's" personal insurance also applies on an excess basis to a covered "auto" hired or rented by your "employee" on your behalf and at your direction, this insurance will be primary to the "employee's" personal insurance.

- 3. AMENDED FELLOW EMPLOYEE EXCLUSION**
EXCLUSION 5. - FELLOW EMPLOYEE - of SECTION II - LIABILITY COVERAGE does not apply if you have workers' compensation insurance in-force covering all of your "employees".

Coverage is excess over any other collectible insurance.

4. HIRED AUTO PHYSICAL DAMAGE COVERAGE

If hired "autos" are covered "autos" for Liability Coverage and if Comprehensive, Specified Causes of Loss, or Collision coverages are provided under this Coverage Form for any "auto" you own, then the Physical Damage Coverages provided are extended to "autos" you hire or borrow, subject to the following limit.

The most we will pay for "loss" to any hired "auto" is:

- (1) \$100,000;
- (2) The actual cash value of the damaged or stolen property at the time of the "loss"; or
- (3) The cost of repairing or replacing the damaged or stolen property,

whichever is smallest, minus a deductible. The deductible will be equal to the largest deductible applicable to any owned "auto" for that coverage. No deductible applies to "loss" caused by fire or lightning. Hired Auto Physical Damage coverage is excess over any other collectible insurance. Subject to the above limit, deductible and excess provisions, we will provide coverage equal to the broadest coverage applicable to any covered "auto" you own.

We will also cover loss of use of the hired "auto" if it results from an "accident", you are legally liable and the lessor incurs an actual financial loss, subject to a maximum of \$1000 per "accident".

This extension of coverage does not apply to any "auto" you hire or borrow from any of your "employees", partners (if you are a partnership), members (if you are a limited liability company), or members of their households.

5. PHYSICAL DAMAGE - ADDITIONAL TEMPORARY TRANSPORTATION EXPENSE COVERAGE

Paragraph A.4.a. of SECTION III - PHYSICAL DAMAGE COVERAGE is amended to provide a limit of \$50 per day and a maximum limit of \$1,000.

6. LOAN/LEASE GAP COVERAGE

Under SECTION III - PHYSICAL DAMAGE COVERAGE, in the event of a total "loss" to a covered "auto", we will pay your additional legal obligation for any difference between the actual cash value of the "auto" at the time of the "loss" and the "outstanding balance" of the loan/lease.

"Outstanding balance" means the amount you owe on the loan/lease at the time of "loss" less any amounts representing taxes; overdue payments; penalties, interest or charges resulting from overdue payments; additional mileage charges; excess wear and tear charges; lease termination fees; security deposits not returned by the lessor; costs for extended warranties, credit life insurance, health, accident or disability insurance purchased with the loan or lease; and carry-over balances from previous loans or leases.

7. AIRBAG COVERAGE

Under Paragraph B. EXCLUSIONS - of SECTION III - PHYSICAL DAMAGE COVERAGE, the following is added:

The exclusion relating to mechanical breakdown does not apply to the accidental discharge of an airbag.

8. ELECTRONIC EQUIPMENT - BROADENED COVERAGE

a. The exceptions to Paragraphs B.4 - EXCLUSIONS - of SECTION III - PHYSICAL DAMAGE COVERAGE are replaced by the following:

Exclusions 4.c. and 4.d. do not apply to equipment designed to be operated solely by use of the power from the "auto's" electrical system that, at the time of "loss", is:

- (1) Permanently installed in or upon the covered "auto";
- (2) Removable from a housing unit which is permanently installed in or upon the covered "auto";
- (3) An integral part of the same unit housing any electronic equipment described in Paragraphs (1) and (2) above; or

The insurance afforded to any such additional insured applies only if the "bodily injury" or "property damage" occurs:

- (1) During the policy period, and
- (2) Subsequent to the execution of such written contract, and
- (3) Prior to the expiration of the period of time that the written contract requires such insurance be provided to the additional insured.

(2) How Limits Apply

If you have agreed in a written contract or written agreement that another person or organization be added as an additional insured on your policy, the most we will pay on behalf of such additional insured is the lesser of:

- (a) The limits of insurance specified in the written contract or written agreement; or
- (b) The Limits of Insurance shown in the Declarations.

Such amount shall be a part of and not in addition to Limits of Insurance shown in the Declarations and described in this Section.

(3) Additional Insureds Other Insurance

If we cover a claim or "suit" under this Coverage Part that may also be covered by other insurance available to an additional insured, such additional insured must submit such claim or "suit" to the other insurer for defense and indemnity.

However, this provision does not apply to the extent that you have agreed in a written contract or written agreement that this insurance is primary and non-contributory with the additional insured's own insurance.

(4) Duties in The Event Of Accident, Claim, Suit or Loss

If you have agreed in a written contract or written agreement that another person or organization be added as an additional insured on your policy, the additional insured shall be required to comply with the provisions in LOSS CONDITIONS 2. - DUTIES IN THE EVENT OF ACCIDENT, CLAIM, SUIT OR LOSS - OF SECTION IV - BUSINESS AUTO CONDITIONS, in the same manner as the Named Insured.

E. Primary and Non-Contributory if Required by Contract

Only with respect to insurance provided to an additional insured in 1.D. - Additional Insured If Required by Contract, the following provisions apply:

(3) Primary Insurance When Required By Contract

This insurance is primary if you have agreed in a written contract or written agreement that this insurance be primary. If other insurance is also primary, we will share with all that other insurance by the method described in Other Insurance 5.d.

(4) Primary And Non-Contributory To Other Insurance When Required By Contract

If you have agreed in a written contract or written agreement that this insurance is primary and non-contributory with the additional insured's own insurance, this insurance is primary and we will not seek contribution from that other insurance.

Paragraphs (3) and (4) do not apply to other insurance to which the additional insured has been added as an additional insured.

When this insurance is excess, we will have no duty to defend the insured against any "suit" if any other insurer has a duty to defend the insured against that "suit". If no other insurer defends, we will undertake to do so, but we will be entitled to the insured's rights against all those other insurers.

When this insurance is excess over other insurance, we will pay only our share of the amount of the loss, if any, that exceeds the sum of:

- (1) The total amount that all such other insurance would pay for the loss in the absence of this insurance; and
- (2) The total of all deductible and self-insured amounts under all that other insurance.

We will share the remaining loss, if any, by the method described in Other Insurance 5.d.

2. AUTOS RENTED BY EMPLOYEES

Any "auto" hired or rented by your "employee" on your behalf and at your direction will be considered an "auto" you hire.

The OTHER INSURANCE Condition is amended by adding the following:

- (4) Necessary for the normal operation of the covered "auto" or the monitoring of the covered "auto's" operating system.

b. Section III – Version CA 00 01 03 10 of the Business Auto Coverage Form, Physical Damage Coverage, Limit of Insurance, Paragraph C.2 and Version CA 00 01 10 01 of the Business Auto Coverage Form, Physical Damage Coverage, Limit of Insurance, Paragraph C are each amended to add the following:

\$1,500 is the most we will pay for "loss" in any one "accident" to all electronic equipment (other than equipment designed solely for the reproduction of sound, and accessories used with such equipment) that reproduces, receives or transmits audio, visual or data signals which, at the time of "loss", is:

- (1) Permanently installed in or upon the covered "auto" in a housing, opening or other location that is not normally used by the "auto" manufacturer for the installation of such equipment;
- (2) Removable from a permanently installed housing unit as described in Paragraph 2.a. above or is an integral part of that equipment; or
- (3) An integral part of such equipment.

c. For each covered "auto", should loss be limited to electronic equipment only, our obligation to pay for, repair, return or replace damaged or stolen electronic equipment will be reduced by the applicable deductible shown in the Declarations, or \$250, whichever deductible is less.

9. EXTRA EXPENSE - BROADENED COVERAGE

Under Paragraph A. - COVERAGE - of SECTION III - PHYSICAL DAMAGE COVERAGE, we will pay for the expense of returning a stolen covered "auto" to you.

10. GLASS REPAIR - WAIVER OF DEDUCTIBLE

Under Paragraph D. - DEDUCTIBLE - of SECTION III - PHYSICAL DAMAGE COVERAGE, the following is added:

No deductible applies to glass damage if the glass is repaired rather than replaced.

11. TWO OR MORE DEDUCTIBLES

Under Paragraph D. - DEDUCTIBLE - of SECTION III - PHYSICAL DAMAGE COVERAGE, the following is added:

If another Hartford Financial Services Group, Inc. company policy or coverage form that is not an automobile policy or coverage form applies to the same "accident", the following applies:

- (1) If the deductible under this Business Auto Coverage Form is the smaller (or smallest) deductible, it will be waived;
- (2) If the deductible under this Business Auto Coverage Form is not the smaller (or smallest) deductible, it will be reduced by the amount of the smaller (or smallest) deductible.

12. AMENDED DUTIES IN THE EVENT OF ACCIDENT, CLAIM, SUIT OR LOSS

The requirement in LOSS CONDITIONS 2.a. - DUTIES IN THE EVENT OF ACCIDENT, CLAIM, SUIT OR LOSS - of SECTION IV - BUSINESS AUTO CONDITIONS that you must notify us of an "accident" applies only when the "accident" is known to:

- (1) You, if you are an individual;
- (2) A partner, if you are a partnership;
- (3) A member, if you are a limited liability company; or
- (4) An executive officer or insurance manager, if you are a corporation.

13. UNINTENTIONAL FAILURE TO DISCLOSE HAZARDS

If you unintentionally fail to disclose any hazards existing at the inception date of your policy, we will not deny coverage under this Coverage Form because of such failure.

14. HIRED AUTO - COVERAGE TERRITORY

Paragraph e. of GENERAL CONDITIONS 7. - POLICY PERIOD, COVERAGE TERRITORY - of SECTION IV - BUSINESS AUTO CONDITIONS is replaced by the following:

- e. For short-term hired "autos", the coverage territory with respect to Liability Coverage is anywhere in the world provided that if the "insured's" responsibility to pay damages for "bodily injury" or "property damage" is determined in a "suit," the "suit" is brought in the United States of America, the territories and possessions of the United States of America, Puerto Rico or Canada or in a settlement we agree to.

15. WAIVER OF SUBROGATION

TRANSFER OF RIGHTS OF RECOVERY AGAINST OTHERS TO US - of SECTION IV - BUSINESS AUTO CONDITIONS is amended by adding the following:

We waive any right of recovery we may have against any person or organization with whom you have a written contract that requires such waiver because of payments we make for damages under this Coverage Form.

16. RESULTANT MENTAL ANGUISH COVERAGE

The definition of "bodily injury" in SECTION V-DEFINITIONS is replaced by the following:

"Bodily injury" means bodily injury, sickness or disease sustained by any person, including mental anguish or death resulting from any of these.

17. EXTENDED CANCELLATION CONDITION

Paragraph 2. of the COMMON POLICY CONDITIONS - CANCELLATION - applies except as follows:

If we cancel for any reason other than nonpayment of premium, we will mail or deliver to the first Named Insured written notice of cancellation at least 60 days before the effective date of cancellation.

18. HYBRID, ELECTRIC, OR NATURAL GAS VEHICLE PAYMENT COVERAGE

In the event of a total loss to a "non-hybrid" auto for which Comprehensive, Specified Causes of Loss, or Collision coverages are provided under this Coverage Form, then such Physical Damage Coverages are amended as follows:

a. If the auto is replaced with a "hybrid" auto or an auto powered solely by electricity or natural gas, we will pay an additional 10%, to a maximum of \$2,500, of the "non-hybrid" auto's actual cash value or replacement cost, whichever is less,

b. The auto must be replaced and a copy of a bill of sale or new lease agreement received by us within 60 calendar days of the date of "loss,"

c. Regardless of the number of autos deemed a total loss, the most we will pay under this Hybrid, Electric, or Natural Gas Vehicle Payment Coverage provision for any one "loss" is \$10,000.

For the purposes of the coverage provision,

a. A "non-hybrid" auto is defined as an auto that uses only an internal combustion engine to move the auto but does not include autos powered solely by electricity or natural gas.

b. A "hybrid" auto is defined as an auto with an internal combustion engine and one or more electric motors; and that uses the internal combustion engine and one or more electric motors to move the auto, or the internal combustion engine to charge one or more electric motors, which move the auto.

19. VEHICLE WRAP COVERAGE

In the event of a total loss to an "auto" for which Comprehensive, Specified Causes of Loss, or Collision coverages are provided under this Coverage Form, then such Physical Damage Coverages are amended to add the following:

In addition to the actual cash value of the "auto", we will pay up to \$1,000 for vinyl vehicle wraps which are displayed on the covered "auto" at the time of total loss. Regardless of the number of autos deemed a total loss, the most we will pay under this Vehicle Wrap Coverage provision for any one "loss" is \$5,000. For purposes of this coverage provision, signs or other graphics painted or magnetically affixed to the vehicle are not considered vehicle wraps.



THIS ENDORSEMENT CHANGES THE POLICY. PLEASE READ IT CAREFULLY.

**ADDITIONAL PERSONS OR ORGANIZATIONS
DESIGNATED AS NAMED INSUREDS**

This endorsement modifies insurance provided under the following:

COMMERCIAL GENERAL LIABILITY COVERAGE PART
PRODUCTS/COMPLETED OPERATIONS LIABILITY COVERAGE PART
OWNERS AND CONTRACTORS PROTECTIVE LIABILITY COVERAGE PART

The following person(s) or organizations(s) are added as Named Insureds under this policy:

STERLING CONSTRUCTION COMPANY, INC.
TEXAS STERLING CONSTRUCTION CO.
RDI FOUNDATION DRILLING
STERLING HOUSTON HOLDINGS, INC.
RHB PROPERTIES, LLC
ROAD AND HIGHWAY BUILDERS, LLC
ROAD AND HIGHWAY BUILDERS, INC.
ROAD AND HIGHWAY BUILDERS OF CALIFORNIA, INC.
RALPH L. WADSWORTH CONSTRUCTION COMPANY, LLC
RALPH L. WADSWORTH CONSTRUCTION COMPANY CO. LP
J. BANICKI CONSTRUCTION, INC.
MYERS & SONS CONSTRUCTION, LP
C & J MYERS, INC.
STERLING HAWAII ASPHALT, LLC
TEXAS CRUSHED CONCRETE
STERLING CONSTRUCTION COMPANY, INC. DBA STERLING DELAWARE HOLDING COMPANY, INC.
MYERS AND SONS / ACC JV

**Waiver of Our Right to Recover
From Others Endorsement**



Policy Number
61 WN QU2060

Named Insured and Address

This endorsement forms a part of the policy as numbered above, issued by THE HARTFORD INSURANCE GROUP company designated therein, and takes effect as of the effective date of said policy unless another effective date is stated herein.

STERLING CONSTRUCTION COMPANY, INC.
ONE HUGHES LANDING
1800 HUGHES LANDING BLVD, SUITE 250
THE WOODLANDS, TX 77380

Effective Date Effective hour is the same as stated
03/01/2015 in the Declarations of the policy.

Endt. No.
19

We have the right to recover our payments from anyone liable for an injury covered by this policy. We will not enforce our right against the person or organization named in the Schedule.

This agreement shall not operate directly or indirectly to benefit anyone not named in the Schedule.

SCHEDULE

ANY PERSON OR ORGANIZATION FROM WHOM YOU ARE REQUIRED BY WRITTEN CONTRACT OR AGREEMENT TO OBTAIN THIS WAIVER OF RIGHTS FROM US.

AIA[®] Document A312[™] – 2010

Bond No. 106307278

Performance Bond

CONTRACTOR:

(Name, legal status and address)
J. BANICKI CONSTRUCTION, INC.
6423 S. Ash Avenue
Tempe, AZ 85283

SURETY:

(Name, legal status and principal place of business)
TRAVELERS CASUALTY AND SURETY
COMPANY OF AMERICA
One Tower Square
Hartford, CT 06183

OWNER:

(Name, legal status and address)
CITY OF GLENDALE
633 E. Broadway
Glendale, CA 91206

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

AIA Document A312-2010 combines two separate bonds, a Performance Bond and a Payment Bond, into one form. This is not a single combined Performance and Payment Bond.

CONSTRUCTION CONTRACT

Date: 6/16/15

Amount: Four Hundred Fifty Seven Thousand Two Hundred Ninety Five and 00/100 Dollars
(\$ 457,295.00)

Description:

(Name and location)
2014/2015 Bridge Maintenance Repair

BOND

Date: 6/18/15

(Not earlier than Construction Contract Date)

Amount: Four Hundred Fifty Seven Thousand Two Hundred Ninety Five and 00/100 Dollars (\$ 457,295.00)

Modifications to this Bond: None See Section 16

CONTRACTOR AS PRINCIPAL

Company:
J. BANICKI CONSTRUCTION, INC.

Signature: 
Name: Mike
and Title: President

(Any additional signatures appear on the last page of this Performance Bond.)

SURETY

Company: (Corporate Seal)
TRAVELERS CASUALTY AND SURETY COMPANY OF AMERICA

Signature: 
Name: Stephanie Whittington, Attorney-in-Fact
and Title:

(FOR INFORMATION ONLY — Name, address and telephone)

AGENT or BROKER:
Aon Risk Services Southwest, Inc.
5555 San Felipe St., Suite 1500
Houston, TX 77056
832-476-6000

OWNER'S REPRESENTATIVE:
(Architect, Engineer or other party:)

§ 1 The Contractor and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner for the performance of the Construction Contract, which is incorporated herein by reference.

§ 2 If the Contractor performs the Construction Contract, the Surety and the Contractor shall have no obligation under this Bond, except when applicable to participate in a conference as provided in Section 3.

§ 3 If there is no Owner Default under the Construction Contract, the Surety's obligation under this Bond shall arise after

- .1 the Owner first provides notice to the Contractor and the Surety that the Owner is considering declaring a Contractor Default. Such notice shall indicate whether the Owner is requesting a conference among the Owner, Contractor and Surety to discuss the Contractor's performance. If the Owner does not request a conference, the Surety may, within five (5) business days after receipt of the Owner's notice, request such a conference. If the Surety timely requests a conference, the Owner shall attend. Unless the Owner agrees otherwise, any conference requested under this Section 3.1 shall be held within ten (10) business days of the Surety's receipt of the Owner's notice. If the Owner, the Contractor and the Surety agree, the Contractor shall be allowed a reasonable time to perform the Construction Contract, but such an agreement shall not waive the Owner's right, if any, subsequently to declare a Contractor Default;
- .2 the Owner declares a Contractor Default, terminates the Construction Contract and notifies the Surety; and
- .3 the Owner has agreed to pay the Balance of the Contract Price in accordance with the terms of the Construction Contract to the Surety or to a contractor selected to perform the Construction Contract.

§ 4 Failure on the part of the Owner to comply with the notice requirement in Section 3.1 shall not constitute a failure to comply with a condition precedent to the Surety's obligations, or release the Surety from its obligations, except to the extent the Surety demonstrates actual prejudice.

§ 5 When the Owner has satisfied the conditions of Section 3, the Surety shall promptly and at the Surety's expense take one of the following actions:

§ 5.1 Arrange for the Contractor, with the consent of the Owner, to perform and complete the Construction Contract;

§ 5.2 Undertake to perform and complete the Construction Contract itself, through its agents or independent contractors;

§ 5.3 Obtain bids or negotiated proposals from qualified contractors acceptable to the Owner for a contract for performance and completion of the Construction Contract, arrange for a contract to be prepared for execution by the Owner and a contractor selected with the Owner's concurrence, to be secured with performance and payment bonds executed by a qualified surety equivalent to the bonds issued on the Construction Contract, and pay to the Owner the amount of damages as described in Section 7 in excess of the Balance of the Contract Price incurred by the Owner as a result of the Contractor Default; or

§ 5.4 Waive its right to perform and complete, arrange for completion, or obtain a new contractor and with reasonable promptness under the circumstances:

- .1 After investigation, determine the amount for which it may be liable to the Owner and, as soon as practicable after the amount is determined, make payment to the Owner; or
- .2 Deny liability in whole or in part and notify the Owner, citing the reasons for denial.

§ 6 If the Surety does not proceed as provided in Section 5 with reasonable promptness, the Surety shall be deemed to be in default on this Bond seven days after receipt of an additional written notice from the Owner to the Surety demanding that the Surety perform its obligations under this Bond, and the Owner shall be entitled to enforce any remedy available to the Owner. If the Surety proceeds as provided in Section 5.4, and the Owner refuses the payment or the Surety has denied liability, in whole or in part, without further notice the Owner shall be entitled to enforce any remedy available to the Owner.

§ 7 If the Surety elects to act under Section 5.1, 5.2 or 5.3, then the responsibilities of the Surety to the Owner shall not be greater than those of the Contractor under the Construction Contract, and the responsibilities of the Owner to the Surety shall not be greater than those of the Owner under the Construction Contract. Subject to the commitment by the Owner to pay the Balance of the Contract Price, the Surety is obligated, without duplication, for

- .1 the responsibilities of the Contractor for correction of defective work and completion of the Construction Contract;
- .2 additional legal, design professional and delay costs resulting from the Contractor's Default, and resulting from the actions or failure to act of the Surety under Section 5; and
- .3 liquidated damages, or if no liquidated damages are specified in the Construction Contract, actual damages caused by delayed performance or non-performance of the Contractor.

§ 8 If the Surety elects to act under Section 5.1, 5.3 or 5.4, the Surety's liability is limited to the amount of this Bond.

§ 9 The Surety shall not be liable to the Owner or others for obligations of the Contractor that are unrelated to the Construction Contract, and the Balance of the Contract Price shall not be reduced or set off on account of any such unrelated obligations. No right of action shall accrue on this Bond to any person or entity other than the Owner or its heirs, executors, administrators, successors and assigns.

§ 10 The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.

§ 11 Any proceeding, legal or equitable, under this Bond may be instituted in any court of competent jurisdiction in the location in which the work or part of the work is located and shall be instituted within two years after a declaration of Contractor Default or within two years after the Contractor ceased working or within two years after the Surety refuses or fails to perform its obligations under this Bond, whichever occurs first. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.

§ 12 Notice to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the page on which their signature appears.

§ 13 When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

§ 14 Definitions

§ 14.1 **Balance of the Contract Price.** The total amount payable by the Owner to the Contractor under the Construction Contract after all proper adjustments have been made, including allowance to the Contractor of any amounts received or to be received by the Owner in settlement of insurance or other claims for damages to which the Contractor is entitled, reduced by all valid and proper payments made to or on behalf of the Contractor under the Construction Contract.

§ 14.2 **Construction Contract.** The agreement between the Owner and Contractor identified on the cover page, including all Contract Documents and changes made to the agreement and the Contract Documents.

§ 14.3 **Contractor Default.** Failure of the Contractor, which has not been remedied or waived, to perform or otherwise to comply with a material term of the Construction Contract.

§ 14.4 **Owner Default.** Failure of the Owner, which has not been remedied or waived, to pay the Contractor as required under the Construction Contract or to perform and complete or comply with the other material terms of the Construction Contract.

§ 14.5 **Contract Documents.** All the documents that comprise the agreement between the Owner and Contractor.

§ 15 If this Bond is issued for an agreement between a Contractor and subcontractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

§ 16 Modifications to this bond are as follows:

(Space is provided below for additional signatures of added parties, other than those appearing on the cover page.)

CONTRACTOR AS PRINCIPAL

SURETY

Company:

(Corporate Seal)

Company:

(Corporate Seal)

Signature: _____

Signature: _____

Name and Title: _____

Name and Title: _____, Attorney-in-Fact

Address: _____

Address: _____



AIA Document A312™ – 2010

Payment Bond

Bond No. 106307278

CONTRACTOR:

(Name, legal status and address)

J. BANICKI CONSTRUCTION, INC.
6423 S. Ash Avenue

Tempe, AZ 85283

SURETY:

(Name, legal status and principal place of business)

TRAVELERS CASUALTY AND SURETY
COMPANY OF AMERICA
One Tower Square
Hartford, CT 06183

This document has important legal consequences. Consultation with an attorney is encouraged with respect to its completion or modification.

Any singular reference to Contractor, Surety, Owner or other party shall be considered plural where applicable.

AIA Document A312-2010 combines two separate bonds, a Performance Bond and a Payment Bond, into one form. This is not a single combined Performance and Payment Bond.

OWNER:

(Name, legal status and address)

CITY OF GLENDALE
633 E. Broadway
Glendale, CA 91206

CONSTRUCTION CONTRACT

Date: 6/16/15

Amount: Four Hundred Fifty Seven Thousand Two Hundred Ninety Five and 00/100 Dollars

(\$ 457,295.00)

Description:

(Name and location)

2014/2015 Bridge Maintenance Repair

BOND

Date: 6/18/15

(Not earlier than Construction Contract Date)

Amount: Four Hundred Fifty Seven Thousand Two Hundred Ninety Five and 00/100 Dollars
(\$ 457,295.00)

Modifications to this Bond: None See Section 18

CONTRACTOR AS PRINCIPAL

Company:
J. BANICKI CONSTRUCTION, INC.

Company: *(Corporate Seal)*
TRAVELERS CASUALTY AND SURETY COMPANY OF AMERICA

Signature: *Mike Abramo*
Name: *Mike Abramo*
and Title: *President*

Signature: *Stepherlie Whittington*
Name: *Stepherlie Whittington, Attorney-in-Fact*
and Title:

(Any additional signatures appear on the last page of this Payment Bond.)

(FOR INFORMATION ONLY — Name, address and telephone)

AGENT or BROKER:

Aon Risk Services Southwest, Inc.
5555 San Felipe St., Suite 1500
Houston, TX 77056
832-476-6000

OWNER'S REPRESENTATIVE:

(Architect, Engineer or other party:)

§ 1 The Contractor and Surety, jointly and severally, bind themselves, their heirs, executors, administrators, successors and assigns to the Owner to pay for labor, materials and equipment furnished for use in the performance of the Construction Contract, which is incorporated herein by reference, subject to the following terms.

§ 2 If the Contractor promptly makes payment of all sums due to Claimants, and defends, indemnifies and holds harmless the Owner from claims, demands, liens or suits by any person or entity seeking payment for labor, materials or equipment furnished for use in the performance of the Construction Contract, then the Surety and the Contractor shall have no obligation under this Bond.

§ 3 If there is no Owner Default under the Construction Contract, the Surety's obligation to the Owner under this Bond shall arise after the Owner has promptly notified the Contractor and the Surety (at the address described in Section 13) of claims, demands, liens or suits against the Owner or the Owner's property by any person or entity seeking payment for labor, materials or equipment furnished for use in the performance of the Construction Contract and tendered defense of such claims, demands, liens or suits to the Contractor and the Surety.

§ 4 When the Owner has satisfied the conditions in Section 3, the Surety shall promptly and at the Surety's expense defend, indemnify and hold harmless the Owner against a duly tendered claim, demand, lien or suit.

§ 5 The Surety's obligations to a Claimant under this Bond shall arise after the following:

§ 5.1 Claimants, who do not have a direct contract with the Contractor,

- .1 have furnished a written notice of non-payment to the Contractor, stating with substantial accuracy the amount claimed and the name of the party to whom the materials were, or equipment was, furnished or supplied or for whom the labor was done or performed, within ninety (90) days after having last performed labor or last furnished materials or equipment included in the Claim; and
- .2 have sent a Claim to the Surety (at the address described in Section 13).

§ 5.2 Claimants, who are employed by or have a direct contract with the Contractor, have sent a Claim to the Surety (at the address described in Section 13).

§ 6 If a notice of non-payment required by Section 5.1.1 is given by the Owner to the Contractor, that is sufficient to satisfy a Claimant's obligation to furnish a written notice of non-payment under Section 5.1.1.

§ 7 When a Claimant has satisfied the conditions of Sections 5.1 or 5.2, whichever is applicable, the Surety shall promptly and at the Surety's expense take the following actions:

§ 7.1 Send an answer to the Claimant, with a copy to the Owner, within sixty (60) days after receipt of the Claim, stating the amounts that are undisputed and the basis for challenging any amounts that are disputed; and

§ 7.2 Pay or arrange for payment of any undisputed amounts.

§ 7.3 The Surety's failure to discharge its obligations under Section 7.1 or Section 7.2 shall not be deemed to constitute a waiver of defenses the Surety or Contractor may have or acquire as to a Claim, except as to undisputed amounts for which the Surety and Claimant have reached agreement. If, however, the Surety fails to discharge its obligations under Section 7.1 or Section 7.2, the Surety shall indemnify the Claimant for the reasonable attorney's fees the Claimant incurs thereafter to recover any sums found to be due and owing to the Claimant.

§ 8 The Surety's total obligation shall not exceed the amount of this Bond, plus the amount of reasonable attorney's fees provided under Section 7.3, and the amount of this Bond shall be credited for any payments made in good faith by the Surety.

§ 9 Amounts owed by the Owner to the Contractor under the Construction Contract shall be used for the performance of the Construction Contract and to satisfy claims, if any, under any construction performance bond. By the Contractor furnishing and the Owner accepting this Bond, they agree that all funds earned by the Contractor in the performance of the Construction Contract are dedicated to satisfy obligations of the Contractor and Surety under this Bond, subject to the Owner's priority to use the funds for the completion of the work.

§ 10 The Surety shall not be liable to the Owner, Claimants or others for obligations of the Contractor that are unrelated to the Construction Contract. The Owner shall not be liable for the payment of any costs or expenses of any Claimant under this Bond, and shall have under this Bond no obligation to make payments to, or give notice on behalf of, Claimants or otherwise have any obligations to Claimants under this Bond.

§ 11 The Surety hereby waives notice of any change, including changes of time, to the Construction Contract or to related subcontracts, purchase orders and other obligations.

§ 12 No suit or action shall be commenced by a Claimant under this Bond other than in a court of competent jurisdiction in the state in which the project that is the subject of the Construction Contract is located or after the expiration of one year from the date (1) on which the Claimant sent a Claim to the Surety pursuant to Section 5.1.2 or 5.2, or (2) on which the last labor or service was performed by anyone or the last materials or equipment were furnished by anyone under the Construction Contract, whichever of (1) or (2) first occurs. If the provisions of this Paragraph are void or prohibited by law, the minimum period of limitation available to sureties as a defense in the jurisdiction of the suit shall be applicable.

§ 13 Notice and Claims to the Surety, the Owner or the Contractor shall be mailed or delivered to the address shown on the page on which their signature appears. Actual receipt of notice or Claims, however accomplished, shall be sufficient compliance as of the date received.

§ 14 When this Bond has been furnished to comply with a statutory or other legal requirement in the location where the construction was to be performed, any provision in this Bond conflicting with said statutory or legal requirement shall be deemed deleted herefrom and provisions conforming to such statutory or other legal requirement shall be deemed incorporated herein. When so furnished, the intent is that this Bond shall be construed as a statutory bond and not as a common law bond.

§ 15 Upon request by any person or entity appearing to be a potential beneficiary of this Bond, the Contractor and Owner shall promptly furnish a copy of this Bond or shall permit a copy to be made.

§ 16 Definitions

§ 16.1 Claim. A written statement by the Claimant including at a minimum:

- .1 the name of the Claimant;
- .2 the name of the person for whom the labor was done, or materials or equipment furnished;
- .3 a copy of the agreement or purchase order pursuant to which labor, materials or equipment was furnished for use in the performance of the Construction Contract;
- .4 a brief description of the labor, materials or equipment furnished;
- .5 the date on which the Claimant last performed labor or last furnished materials or equipment for use in the performance of the Construction Contract;
- .6 the total amount earned by the Claimant for labor, materials or equipment furnished as of the date of the Claim;
- .7 the total amount of previous payments received by the Claimant; and
- .8 the total amount due and unpaid to the Claimant for labor, materials or equipment furnished as of the date of the Claim.

§ 16.2 Claimant. An individual or entity having a direct contract with the Contractor or with a subcontractor of the Contractor to furnish labor, materials or equipment for use in the performance of the Construction Contract. The term Claimant also includes any individual or entity that has rightfully asserted a claim under an applicable mechanic's lien or similar statute against the real property upon which the Project is located. The intent of this Bond shall be to include without limitation in the terms "labor, materials or equipment" that part of water, gas, power, light, heat, oil, gasoline, telephone service or rental equipment used in the Construction Contract, architectural and engineering services required for performance of the work of the Contractor and the Contractor's subcontractors, and all other items for which a mechanic's lien may be asserted in the jurisdiction where the labor, materials or equipment were furnished.

§ 16.3 Construction Contract. The agreement between the Owner and Contractor identified on the cover page, including all Contract Documents and all changes made to the agreement and the Contract Documents.

§ 16.4 Owner Default. Failure of the Owner, which has not been remedied or waived, to pay the Contractor as required under the Construction Contract or to perform and complete or comply with the other material terms of the Construction Contract.

§ 16.5 Contract Documents. All the documents that comprise the agreement between the Owner and Contractor.

§ 17 If this Bond is issued for an agreement between a Contractor and subcontractor, the term Contractor in this Bond shall be deemed to be Subcontractor and the term Owner shall be deemed to be Contractor.

§ 18 Modifications to this bond are as follows:

(Space is provided below for additional signatures of added parties, other than those appearing on the cover page.)

CONTRACTOR AS PRINCIPAL

SURETY

Company:

(Corporate Seal)

Company:

(Corporate Seal)

Signature: _____

Signature: _____

Name and Title: ,

Name and Title: , Attorney-in-Fact

Address:

Address:



POWER OF ATTORNEY

Farmington Casualty Company
Fidelity and Guaranty Insurance Company
Fidelity and Guaranty Insurance Underwriters, Inc.
St. Paul Fire and Marine Insurance Company
St. Paul Guardian Insurance Company

St. Paul Mercury Insurance Company
Travelers Casualty and Surety Company
Travelers Casualty and Surety Company of America
United States Fidelity and Guaranty Company

Attorney-In Fact No. 228950

Certificate No. 006191215

KNOW ALL MEN BY THESE PRESENTS: That Farmington Casualty Company, St. Paul Fire and Marine Insurance Company, St. Paul Guardian Insurance Company, St. Paul Mercury Insurance Company, Travelers Casualty and Surety Company, Travelers Casualty and Surety Company of America, and United States Fidelity and Guaranty Company are corporations duly organized under the laws of the State of Connecticut, that Fidelity and Guaranty Insurance Company is a corporation duly organized under the laws of the State of Iowa, and that Fidelity and Guaranty Insurance Underwriters, Inc., is a corporation duly organized under the laws of the State of Wisconsin (herein collectively called the "Companies"), and that the Companies do hereby make, constitute and appoint

Michael J. Herrod, Wendy W. Stuckey, Margaret Buboltz, Lisa A. Ward, Donna L. Williams, Jennifer Copeland, David Wightman, Stephenie Whittington, Anoop Chawla Adlakha, Lupe Tyler, Nancy Thomas, Vanessa Dominguez, and Myisha Jefferson

of the City of Houston, State of Texas, their true and lawful Attorney(s)-in-Fact, each in their separate capacity if more than one is named above, to sign, execute, seal and acknowledge any and all bonds, recognizances, conditional undertakings and other writings obligatory in the nature thereof on behalf of the Companies in their business of guaranteeing the fidelity of persons, guaranteeing the performance of contracts and executing or guaranteeing bonds and undertakings required or permitted in any actions or proceedings allowed by law.

IN WITNESS WHEREOF, the Companies have caused this instrument to be signed and their corporate seals to be hereto affixed, this 10th day of March, 2015.

Farmington Casualty Company
Fidelity and Guaranty Insurance Company
Fidelity and Guaranty Insurance Underwriters, Inc.
St. Paul Fire and Marine Insurance Company
St. Paul Guardian Insurance Company

St. Paul Mercury Insurance Company
Travelers Casualty and Surety Company
Travelers Casualty and Surety Company of America
United States Fidelity and Guaranty Company



State of Connecticut
City of Hartford ss.

By: [Signature]
Robert L. Raney, Senior Vice President

On this the 10th day of March, 2015, before me personally appeared Robert L. Raney, who acknowledged himself to be the Senior Vice President of Farmington Casualty Company, Fidelity and Guaranty Insurance Company, Fidelity and Guaranty Insurance Underwriters, Inc., St. Paul Fire and Marine Insurance Company, St. Paul Guardian Insurance Company, St. Paul Mercury Insurance Company, Travelers Casualty and Surety Company, Travelers Casualty and Surety Company of America, and United States Fidelity and Guaranty Company, and that he, as such, being authorized so to do, executed the foregoing instrument for the purposes therein contained by signing on behalf of the corporations by himself as a duly authorized officer.

In Witness Whereof, I hereunto set my hand and official seal.
My Commission expires the 30th day of June, 2016.



[Signature]
Marie C. Tetreault, Notary Public

This Power of Attorney is granted under and by the authority of the following resolutions adopted by the Boards of Directors of Farmington Casualty Company, Fidelity and Guaranty Insurance Company, Fidelity and Guaranty Insurance Underwriters, Inc., St. Paul Fire and Marine Insurance Company, St. Paul Guardian Insurance Company, St. Paul Mercury Insurance Company, Travelers Casualty and Surety Company, Travelers Casualty and Surety Company of America, and United States Fidelity and Guaranty Company, which resolutions are now in full force and effect, reading as follows:

RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President, any Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary may appoint Attorneys-in-Fact and Agents to act for and on behalf of the Company and may give such appointee such authority as his or her certificate of authority may prescribe to sign with the Company's name and seal with the Company's seal bonds, recognizances, contracts of indemnity, and other writings obligatory in the nature of a bond, recognizance, or conditional undertaking, and any of said officers or the Board of Directors at any time may remove any such appointee and revoke the power given him or her; and it is

FURTHER RESOLVED, that the Chairman, the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President may delegate all or any part of the foregoing authority to one or more officers or employees of this Company, provided that each such delegation is in writing and a copy thereof is filed in the office of the Secretary; and it is

FURTHER RESOLVED, that any bond, recognizance, contract of indemnity, or writing obligatory in the nature of a bond, recognizance, or conditional undertaking shall be valid and binding upon the Company when (a) signed by the President, any Vice Chairman, any Executive Vice President, any Senior Vice President or any Vice President, any Second Vice President, the Treasurer, any Assistant Treasurer, the Corporate Secretary or any Assistant Secretary and duly attested and sealed with the Company's seal by a Secretary or Assistant Secretary; or (b) duly executed (under seal, if required) by one or more Attorneys-in-Fact and Agents pursuant to the power prescribed in his or her certificate or their certificates of authority or by one or more Company officers pursuant to a written delegation of authority; and it is

FURTHER RESOLVED, that the signature of each of the following officers: President, any Executive Vice President, any Senior Vice President, any Vice President, any Assistant Vice President, any Secretary, any Assistant Secretary, and the seal of the Company may be affixed by facsimile to any Power of Attorney or to any certificate relating thereto appointing Resident Vice Presidents, Resident Assistant Secretaries or Attorneys-in-Fact for purposes only of executing and attesting bonds and undertakings and other writings obligatory in the nature thereof, and any such Power of Attorney or certificate bearing such facsimile signature or facsimile seal shall be valid and binding upon the Company and any such power so executed and certified by such facsimile signature and facsimile seal shall be valid and binding on the Company in the future with respect to any bond or understanding to which it is attached.

I, Kevin E. Hughes, the undersigned, Assistant Secretary, of Farmington Casualty Company, Fidelity and Guaranty Insurance Company, Fidelity and Guaranty Insurance Underwriters, Inc., St. Paul Fire and Marine Insurance Company, St. Paul Guardian Insurance Company, St. Paul Mercury Insurance Company, Travelers Casualty and Surety Company, Travelers Casualty and Surety Company of America, and United States Fidelity and Guaranty Company do hereby certify that the above and foregoing is a true and correct copy of the Power of Attorney executed by said Companies, which is in full force and effect and has not been revoked.

IN TESTIMONY WHEREOF, I have hereunto set my hand and affixed the seals of said Companies this 18th day of June, 2015.

THIS POWER OF ATTORNEY IS INVALID WITHOUT THE RED BORDER

Kevin E. Hughes
Kevin E. Hughes, Assistant Secretary



To verify the authenticity of this Power of Attorney, call 1-800-421-3880 or contact us at www.travelersbond.com. Please refer to the Attorney-In-Fact number, the above-named individuals and the details of the bond to which the power is attached.

CITY OF GLENDALE, ARIZONA
PUBLIC WORKS/ENGINEERING DEPARTMENT

CONTRACTOR'S AFFIDAVIT
REGARDING
SETTLEMENT OF CLAIMS

PROJECT 131423 - 2014/2015 BRIDGE MAINTENANCE REPAIR - VARIOUS LOCATIONS

To the City of Glendale, Arizona

Gentlemen:

This is to certify that all lawful claims for materials, rental of equipment and labor used in connection with the construction of the above project, whether by subcontractor or claimant in person, have been duly discharged.

The undersigned, for the consideration of \$ _____, as set out in the final pay estimate, as full and complete payment under the terms of the contract, hereby waives and relinquishes any and all further claims or right of lien under, in connection with, or as a result of the above described project. The undersigned further agrees to indemnify and save harmless the City of Glendale against any and all liens, claims of liens, suits, actions, damages, charges, costs, litigation expenses, attorneys' fees and any other and expenses whatsoever, which said City may suffer arising out of the failure of the undersigned to pay for all labor performance and materials furnished for the performance of said installation.

Signed and dated at _____, this ____ day of _____, 20__.

Contractor

By _____

STATE OF ARIZONA)
) ss.
COUNTY OF MARICOPA)

The foregoing instrument was subscribed and sworn to before me this ____ day of _____, 20

Notary Public

My Commission Expires: _____

SUPPLEMENTAL GENERAL CONDITIONS

1. GENERAL: By Ordinance No. 1110 New Series, the City of Glendale adopted the "Uniform Standard Specifications for Public Works Construction," which are sponsored and distributed by the Maricopa Association of Governments. Copies of these documents, with revisions, are on file in the office of the City Engineer of the City of Glendale, and are hereby made a part of these Contract Documents.

Whenever in the Uniform Standard Specifications, the words "The Contracting Agency" are used, the meaning shall be the City of Glendale.

In all cases where ASTM, AASHTO, AWWA, USAG, Federal, City of Phoenix, MAG Specifications, Maricopa County, Arizona State Highway, City of Glendale or other standard specifications are referred to, unless otherwise stated, revisions, supplements or addenda issued on or before the date of this contract, shall prevail. In the event of any conflict between these project specifications and the requirements of the plans, detail drawings, MAG Standard Details and Specifications, these project specifications shall prevail.

2. DEFINITIONS: The following terms, as used in or pertaining to the Contract Documents, are defined as follows:

CITY: The word "City" refers to the City of Glendale, Arizona. The official representative of said City in these proceedings shall be the City Engineer.

CONTRACTOR: The word "Contractor" means the person, firm, or corporation with whom the Contract is made by the City.

MATERIALS: The term "Materials" includes, in addition to materials incorporated in the project, equipment and other material used and/or consumed in the performance of the work.

SUBCONTRACTOR: The word "Subcontractor" includes those having a direct contract with the Contractor and those who furnish material worked to a special design according to the plans and/or specifications for this work, but does not include those who merely furnish materials not so worked.

ENGINEER: The word "Engineer" means a person, firm or corporation duly authorized by the City, to act for the City in staking out the work, inspecting materials and construction, and interpreting plans and specifications.

CONTRACT DOCUMENTS: The words "Contract Documents" mean the Notice to Contractors, Information for Bidders, "Uniform Standard Specifications for Public Works Construction," MAG General Conditions, Supplemental General Conditions, Special Provisions, Supplemental Specifications, Proposal, Contract, Payment Bond, Performance Bond, Certificates of Insurance, Plans and Addenda thereto.

3. PROPOSAL QUANTITIES: It is expressly understood and agreed by the parties hereto that the quantities of the various classes of work to be done and material to be furnished under this Contract, which have been estimated as stated in the Proposal, are only approximate and are to be used SOLELY for the purpose of comparing, on a consistent basis, the proposals offered for the work under this Contract; and the Contractor further agrees that the City will not be held responsible if any of the quantities shall be found incorrect; and the Contractor will not make any claim for damages or for loss of profits because of a difference between the quantities of the various classes of work as estimated and the work actually done. If any error, omission, or mis-statement is found to occur in the estimated quantities, the same shall not invalidate this Contract or release the Contractor from the execution and completion of the whole or any part of the work in accordance with the specifications and the plans herein mentioned, or for the prices herein agreed upon and fixed therefore, or excuse him from any of the obligations or liabilities hereunder, or entitle him to any damages or compensation except as may be provided for in this Contract.

4. WITHDRAWAL OF PROPOSALS: No proposal shall be withdrawn following the opening and reading of the bids for a period of 50 days from the date of opening without the consent of the contracting agency through the body or agent duly authorized to accept or reject the proposal.

5. LOSSES AND DAMAGES: All loss or damage arising out of the nature of the work to be done or from the action of the elements, or from any unforeseen circumstances in the prosecution of the same, or from any unusual obstructions or difficulties which may be encountered in and/or during the prosecution of the work, or from any casualty whatsoever of every description, shall be sustained and borne by the Contractor at his own cost and expense except as otherwise provided by the contract documents or the laws of the State of Arizona.

6. DUST PREVENTION: The Contractor shall take whatever steps, procedures or means required to prevent abnormal dust conditions due to his construction operations in connection with this contract. The dust control measures shall be maintained at all times during construction of the project, to the satisfaction of the Engineer, in accordance with the requirements of the "Maricopa County Health Department Air Pollution Control Regulations" which have been adopted pursuant to A.R.S. § 36-779.

The Contractor shall be required to obtain the necessary permit from the Maricopa County Air Pollution Control Bureau, 1001 N. Central Ave., Phoenix, Arizona 85004 - telephone (602) 506-6727.

7. EXCESS MATERIAL: Excess material shall be removed from the work site and wasted at a location approved by the Engineer. Broken concrete and asphalt may be delivered to the Glendale Sanitary Landfill located at 115th Avenue and Glendale Avenue. The prevailing regulations and fee schedule will not be waived for work under this project. All materials, to be disposed of at the landfill, shall be weighed and disposed of at the prevailing rate.

8. STOCKPILE OF MATERIALS: The Contractor may place or stockpile materials in the public right-of-way, if approved by the Engineer, provided they do not prevent access to adjacent properties or prevent compliance with traffic regulations.

Traffic shall not be required to travel over stockpiled materials, and proper dust control shall be maintained.

9. REFUSE COLLECTION ACCESS: At any time the project construction shall require the closure or disruption of traffic in any roadway, alley, or refuse collection easement such that normal refuse collection will be interfered with, the Contractor shall, at least 48 hours prior to causing such closure or disruption, make arrangements with the Field Operations Department in order that refuse collection service can be maintained.

10. CLEAN-UP: After all work under this contract is completed, the Contractor shall remove all loose concrete, lumber, wire, reinforcing, debris, and other materials not incorporated in the work, from the site of the work. Clean-up shall include the removal of all excess pointing mortar materials within pipes and removal of over-size rocks and boulders left after finish grading. The contractor shall provide for the legal disposal of all waste products, debris, etc., and shall make necessary arrangements for such disposal.

11. SHOP DRAWINGS: The Contractor shall provide shop drawings as may be necessary for the prosecution of the work as required by the contract documents. The Engineer shall promptly review all shop drawings. The Engineer's approval of any shop drawing shall not release the Contractor from responsibility for deviations from the contract documents. The approval of any shop drawing which substantially deviates from the requirements of the contract documents shall be evidenced by a change order.

When submitted for the Engineer's review, shop drawings shall bear the contractor's certification that he has reviewed, checked, and approved the shop drawings and that they are in conformance with the requirements of the contract documents.

Portions of the work requiring a shop drawing or sample submission shall not begin until the shop drawing or sample submission has been approved by the Engineer. A copy of each approved shop drawing and each approved sample shall be kept in good order by the Contractor at the site and shall be available to the Engineer.

12. PROTECTION OF FINISHED OR PARTIALLY FINISHED WORK: The Contractor shall properly guard and protect all finished or partially finished work, and shall be responsible for the same until the entire contract is completed and accepted, in writing, by the City. The Contractor shall turn over the entire work in full accordance with the specifications before final settlement shall be made.

13. STATUS OF EMPLOYEES: Contractor shall be responsible for assuring the legal working status of its employees and its subcontractor's employees.

14. LAWS AND REGULATIONS: This Contract shall be governed by and constructed in accordance with the laws of the State of Arizona. The Contractor shall keep himself fully informed of all existing and future City and County Ordinances and Regulations and State and Federal Laws and Occupational Safety and Health Standards (OSHA) in any manner affecting the work herein specified. He shall at all times observe and comply with said Ordinances, Regulations, or Laws.

15. PERMITS: The City has obtained certain required permits which are included in the project specifications, but it will be the duty of the Contractor to determine that all the necessary permits have been obtained. The Contractor shall, at his own expense, obtain all required permits which have not been furnished by the City. A no-fee permit will be issued for work in the City of Glendale right-of-way and easement. (Also see Paragraph 7. Dust Prevention.)

16. ELECTRIC POWER AND WATER: The Contractor shall make his own arrangements for electric power and water. Subject to the convenience of the City, he may be permitted to connect to existing facilities where available, but he shall meter and bear the cost of such power or water. Fire hydrant meters may be obtained from the City of Glendale. Installation and removal of meters should be scheduled through the City's Water Services/Utilities Division at 930-2700. For details and current rates, please visit <http://www.glendaleaz.com/CrossConnection/firehydrantmeterprogram.cfm>.

17. SURVEY CONTROL POINTS AND MONUMENTS: Existing survey monuments indicated on the plans or found during construction shall be protected by the Contractor, and in the event removal is necessary, removal and replacement shall be performed by permission of the Engineer, under direct supervision of the Engineer or his authorized representative. Survey monuments shall be constructed to conform to the requirements of MAG Specifications, Section 405, and Standard Details.

18. EXISTING UTILITIES: The Contractor is hereby advised that the location of all utilities, as shown on the plans, may not be complete nor exact and the Contractor shall satisfy himself as to the exact location of the utilities by contacting Blue Stake or the utility companies before proceeding with the work. After the underground utilities are located by Blue Stake or the utility company, the contractor shall excavate in a careful and prudent manner to prevent unwillful damage to the underground utilities.

In the event the Contractor or its Subcontractor damages an existing, properly identified underground City of Glendale water or sewer line, the Contractor shall be responsible for the repairs at its expense.

The exact location of all existing underground service utilities, whether or not indicated on the plans, shall be determined by the Contractor at no expense to the City, and he shall conduct his work so as to prevent interruption of service or damage to them.

The Contractor shall protect existing utility services and be responsible for their replacement if damaged by him, or to make necessary adjustment in their location, if required, in order to complete the work for his Contract.

Utility companies and other interested parties have been provided with construction plans and the

construction schedule for this project. The Contractor shall comply with MAG Specifications 105.6 to cooperate with the utility companies.

19. MAINTENANCE OF IRRIGATION FACILITIES: Where irrigation facilities interfere with construction, the Contractor shall remove and replace the affected irrigation facilities to its original condition. Final acceptance of replaced facilities will depend upon final approval of the Engineer.

20. OVERHEAD UTILITY LINES AND POLES: Contractor is advised that when work around overhead lines and poles is required on a project the Contractor is required to coordinate with Utility Companies who own and operate overhead lines and poles. The coordination may include, but not be limited to the following activities: pole bracing, de-energizing of lines, and temporary relocations. Contractor is responsible to contact the applicable Utility Company representative and discuss his proposed construction methods; in order to determine what actions the Utility Company must take and the costs related to those actions. The Contractor shall include these costs in the applicable bid items for this project.

The primary and the backup representatives for this review and cost determinations are as follows:

Arizona Public Service:	Mr. Bobby Garza	602-371-7989
Qwest:	Mr. Ron Floyd	602-630-1932
Salt River Project:	Mr. Tim Rinn	602-236-8694
Salt River Project:	Ms. Mariann Ward	602-236-6389
Cox Communications:	Mr. Ron Pint	623-328-3529
Cox Communications:	Ms. Linda Facio	623-328-3500

21. SOUTHWEST GAS FACILITIES EXPOSED DURING CONSTRUCTION: The Contractor, upon exposing a gas line during construction, shall call SOUTHWEST GAS at 602-271-4277. The Southwest Gas patrolman will respond, usually within an hour, to inspect the line. Minor cuts or abrasions to the pipe coating will be rewrapped and tracer wire will be reconnected at no cost to the City.

22. UNDERGROUND UTILITIES' BEDDING: All water, sewer, storm drain, irrigation and other conduits installed within the City of Glendale shall be bedded from bottom of excavation to one foot above the pipe with granular bedding material meeting the requirements of Section 601.4.6 of MAG Uniform Standard Specifications. The initial bedding under the pipe shall follow City of Glendale Detail G-690.

23. SEWER SERVICE LINES: The Contractor shall be responsible for locating, and protecting from damage during construction, all sewer service lines within the project which are not owned by the City. Contractor will be permitted to review the "as-builts" to assist Contractor in locating the non-City owned sewer service lines. These "as-builts" were prepared, and supplied to the City, by private developers or contractors who installed the non-City owned sewer service lines. Therefore, the City does not guarantee or warranty the accuracy of such "as-builts" and the contractor, as a condition for being allowed to review such "as-builts", hereby agrees to hold the City harmless for any and all damages or other expenses contractor may incur as a result of any inaccuracies or incorrect information in these "as-builts".

24. RIGHTS-OF-WAY: The City will provide rights-of-way and easements for all work specified in this Contract, and the Contractor shall not enter or occupy with man, tools, equipment or materials any private ground outside the property of the City of Glendale, Maricopa County, Arizona, without the consent of the property owner.

25. SUBCONTRACTS: Subcontracts shall be in accordance with, and the Contractor shall be bound by, the following provisions:

All subcontracts shall be subject to the approval of the City.

All subcontracts shall be in writing and shall provide that all work to be performed thereunder shall be performed in accordance with the terms of the Contract.

Certified copies of any and all subcontracts shall be furnished to the City Engineering Department; however, prices may be omitted.

Subcontracts shall conform to the regulations governing employment of labor.

The subcontracting of any part of the work will in no way relieve the Contractor of his responsibility under the Contract.

26. **PRE-CONSTRUCTION CONFERENCE:** After completion of the Contract Documents, to include bonds, insurance and signatures, and prior to the commencement of any work on the project, the Engineer will schedule a Pre-Construction Conference. This will be held at the City of Glendale, 5850 West Glendale Avenue, Glendale, Arizona.

The purpose of this Conference is to establish a working relationship between the Contractor, Utility Companies, and the Engineer. The agenda will include critical elements of the construction schedule, procedures for handling shop drawings and other submittals, cost breakdown of major lump sum items, payment application and processing, coordination with the involved utility companies, emergency telephone numbers for all representatives involved in the course of construction, and establishment of the Notice to Proceed date.

Minimum attendance by the Contractor shall be a responsible official of the company/corporation, who is authorized to execute and sign documents on behalf of the company/corporation.

27. OVERTIME:

Regular Work Hours: The work required to be performed by the Plans and Specifications for the Project shall be performed only during regular working hours, unless the City has authorized overtime work in accordance with the procedures set forth below. Regular working hours shall be defined as one 8-1/2 hour shift per day, Monday through Friday, or, upon prior approval of the City, one 10-1/2 hour shift per day on a compressed four day work week during Monday through Friday. Regular working hours shall not include Saturdays, Sundays or City recognized legal holidays.

Authorization and Costs: If the Contractor desires to schedule work for times other than regular work hours (overtime), the Contractor shall make a written request to the City at least two business days prior to the scheduled overtime. The City reserves the right to deny the request to work overtime based on the best interest and needs of the City. If an overtime request is denied, the City may, at its sole discretion, extend the contract time at no additional costs to the City.

In the event the Contractor does perform work overtime, with or without the prior approval of the City, the Contractor shall be responsible to the City for all additional costs that may be incurred by the City as a result of the Contractor's overtime work, including costs for engineering, inspections, testing, surveying and construction administration, all in accordance with MAG Section 108.5. However, the Contractor shall not be responsible for City's costs incurred as a result of overtime work requested by the City or overtime work resulting from an emergency which is not the responsibility of the Contractor or its employees, subcontractors or suppliers. The City's cost will be billed directly to the Contractor or may, at the City's option, be deducted from monies due the Contractor.

28. **CONTRACTOR'S CONSTRUCTION SCHEDULE:** Concurrently, with the execution of the contract and prior to the pre-construction conference, the Contractor shall submit a preliminary schedule for the Engineer's review and acceptance. The schedule shall be in sufficient detail to allow the Engineer to determine if the proposed schedule will conform to an acceptable program of construction operations, as determined by the contracting agency. Within ten calendar days after the preliminary schedule, described above, has been accepted by the Engineer, the Contractor shall submit a progress schedule, utilizing the critical path method scheduling technique, showing the order in which he proposes to carry out the work, the dates on which he will start each phase of the work, and the contemplated date for completion of each phase. The Contractor shall not be permitted to commence construction until the schedule complying with this paragraph has been submitted to the City. The Contractor will not be granted any extension to the contract time or compensation for any

damages as a result of the City's refusal to allow Contractor to commence construction until the critical path method progress schedule has been submitted and accepted by the Engineer.

The critical path method (CPM) scheduling technique requires a breakdown of the entire work into individual tasks and an analysis of the number of days required to perform each task. The schedule submitted to the City should highlight and identify the critical path for the project. After the work is in progress, the Contractor shall submit supplementary progress schedules, using the critical path method technique, of the progress to date and projection for completion. The supplementary progress schedules shall be submitted with each pay request in accordance with the paragraph, "Payments to Contractors," of these Supplemental General Conditions. The progress schedules shall be subject to the acceptance of the Engineer. In the event the Contractor fails to submit a supplementary progress schedule acceptable to the Engineer, the City may withhold further progress payments to the Contractor until the Contractor submits an acceptable supplementary progress schedule, which is accepted by the Engineer, to the City. Schedule changes requiring an increase in the City's engineering personnel on the project shall not be put into effect until the Engineer has approved such increase and made arrangements for the required additional personnel.

29. CHARACTER OF WORKMEN: None but skilled foremen and workmen shall be employed on work requiring special qualifications. When required by the Engineer, the Contractor shall discharge any person who is, in the opinion of the Engineer, disorderly, dangerous, insubordinate, incompetent, or otherwise objectionable. The Contractor shall keep the City harmless from damages or claims for compensation that may occur in the enforcement of this section of the specifications.

30. HINDRANCES AND DELAYS: Except as otherwise provided herein, no charge shall be made by the Contractor for hindrances or delays from any cause during the progress of the work embraced in this Contract; but such delays, if due to no fault or neglect of the Contractor, shall entitle the Contractor to an extension of time allowed for completing the work, sufficient to compensate for the delay, the amount of the delay to be determined by the Engineer, provided the Contractor shall give said Engineer immediate notice in writing of the cause of such delay.

30.1 Delay: In the event of a delay for which the City is solely responsible, which is unreasonable under the circumstances and which was not within the contemplation of City and Contractor at the time this Contract is executed, City and Contractor shall negotiate, in good faith, a payment by the City to Contractor for the expenses incurred by Contractor as a result of such delay, in accordance with the City of Glendale Engineering Department's POLICY STATEMENT FOR CALCULATING DELAYS AND DAMAGES. This provision shall not be construed to void any provision in the contract which requires notice of delay or provides for liquidated damages. However, if the delay is the result of any act or neglect of a third party, including the architect, engineer or other contractor employed by the City, or by labor disputes, fire, unusual delay in transportation, adverse weather conditions not reasonably foreseeable, unavoidable casualties, or any causes beyond the Contractor's control, the Contractor shall not be entitled to any payments or compensation for expenses incurred as a result of such delay, but the Contract Time shall be extended by Change Order for such reasonable time as the Engineer may determine. No extension or compensation will be granted for any delay which is the result, wholly or partially, of any act or neglect of Contractor or any Subcontractor hired by Contractor.

31. LIQUIDATED DAMAGES:

31.1 Should the contractor fail to substantially complete the work under this contract within the time for completion stated in the paragraph "Time of Completion," in the Information for Bidders, then the contractor shall pay the City of Glendale, Arizona, liquidated damages, pursuant to the provisions of Section 108.9, Standard Specifications for Public Works Construction, Maricopa Association of Governments, until the work is substantially complete.

31.2 Should the contractor fail to fully and finally complete the work under this contract within the time for completion set forth in the paragraph "Time of Completion," in the Information for Bidders, even though the contractor has achieved substantial completion of the work within such time, then the contractor shall pay the City of Glendale, liquidated damages (pursuant to the provisions of Section

108.9, Standard Specifications for Public Works Construction, Maricopa Association of Governments), in an amount equal to 100% of the applicable liquidated damage rate set forth in MAG Section 108.9 for each and every calendar day of delay until the work is fully and finally complete and accepted.

31.3 The date of substantial completion shall be the date when the work is sufficiently complete, in accordance with the contract documents, so the owner can fully occupy and utilize the work or designated portion thereof for the use for which it is intended, with all the project's parts and systems operable as required by the contract documents and all the work is complete, accessible, operable, and usable by the owner for its intended purpose(s), and all parts, systems and sitework are 100% complete and cleaned for the owner's use. Only incidental corrective work and final cleaning (if required), beyond cleaning needed for the owner's full use, may remain for final completion.

31.4 Full and final completion shall be that date when all work under the project, including incidental corrective work under punch list and final cleaning, has been completed and the entire project is accepted by the owner.

32. PAYMENTS TO CONTRACTOR: The measurements of quantities and the payments to the Contractor shall be in accordance with MAG Uniform Standard Specifications for Public Works Construction, Part 100 - General Conditions, Section 109 - Measurements and Payments.

Payments will be made on the basis of itemized, monthly statements prepared by the City and signed by the Contractor. The Contractor shall submit an itemized, duly certified and approved estimate for work completed through the last day of the preceding month in accordance with MAG Specifications, as amended by these Supplemental General Conditions. Upon approval of the pay estimate, the City will mail the check directly to the Contractor.

The pay estimate shall be accompanied by an updated progress schedule as required by these Supplemental General Conditions and a cash flow report when required by the Special Provisions. Approval of progress payments shall be conditional upon submittal of progress schedules and cash flow reports, when required, which are acceptable to the Engineer.

Upon 100% completion and acceptance of the project, and with the request for final payment, the Contractor shall complete and submit the "Contractor's Affidavit Regarding Settlement of Claims" form which is included in these specifications. Before final payment and release of retention, Contractor must arrange for its Surety to provide the City with a fully executed AIA Consent of Surety form. To avoid delays in the final payment, the Surety may send the Consent of Surety directly to the City via fax at (623) 915-2861, and mail the original to the City of Glendale Engineering Department, 5850 West Glendale Avenue, Glendale, Arizona 85301. Should any ambiguity arise between the Contract and these Conditions, the provisions of the Contract shall prevail.

33. WARRANTY: This project shall have a 2 year warranty. The warranty period shall begin upon final acceptance of the work by the City of Glendale.

END OF SUPPLEMENTAL GENERAL CONDITIONS

SPECIAL PROVISIONS

1. **SCOPE OF WORK:** Project includes various repairs of approximately 6 transportation bridges at various locations. Repairs include, but are not limited to, removal/replacement of structural concrete/steel, repair of signage, guard/pedestrian rail repairs, traffic control and additional miscellaneous work.

2. **DEFINITIONS:**

A. **Section:** Reference to a Section on the plans or in these Specifications shall mean a Section of the Uniform Standard Specifications for Public Works Construction, sponsored and distributed by Maricopa Association of Governments (MAG), latest revision. The provisions of MAG Uniform Standard Specifications and Details for Public Works Construction, which are not altered or modified by the drawings or by these Special Provisions or by any subsequently issued Addendum, shall apply to the contract even though the Contractor's attention is not specifically drawn to such provisions.

B. **Standard Detail:** Reference to a MAG Standard Detail (MAG S.D.) on the plans or in these specifications shall mean a standard detail drawing in the latest revision of the Uniform Standard Specifications for Public Works Construction, sponsored and distributed by Maricopa Association of Governments. City of Glendale Standard Detail (C.O.G. S.D.) shall mean a standard detail drawing in the City of Glendale's Engineering Design and Construction Standards, latest revision. City of Phoenix Standard Detail (C.O.P. S.D.) shall mean a standard detail drawing in the Phoenix Supplemental Standard Details for Public Works Construction, latest revision.

3. **SUSPENSION OF WORK:** The Engineer reserves the right to suspend the work wholly or in part if deemed necessary for the best interest of the City. This suspension will be without compensation to the Contractor, other than to adjust the contract time in accordance with MAG Section 108.

4. **COMPLIANCE WITH MANUFACTURER'S INSTRUCTIONS:** In all instances wherein the item and/or specifications require installation or construction in accordance with either manufacturer's or supplier's recommendations and/or instructions, said recommendations and/or instructions shall be submitted with the applicable portions clearly marked for approval prior to the commencement of work on that item or portion of the contract.

5. **TRAFFIC REGULATIONS:**

5.1 All traffic affected by this construction shall be regulated in accordance with the City of Phoenix "Traffic Barricade Manual," the "Manual of Uniform Traffic Control Devices" and these Special Provisions. The following traffic restrictions are minimum requirements throughout the construction period:

5.1.1 All references in the City of Phoenix "Traffic Barricade Manual" and the "Manual of Uniform Traffic Control Devices" to "arterial" and/or "collector" streets shall mean "arterial and/or major arterial" streets and are referred to as "major" streets in the following sections.

5.1.2 A minimum of two travel lanes (one for each direction) shall be maintained open to traffic at all times on all major streets. All work that enters or crosses a major street must be done at times other than 6:00 a.m. to 8:30 a.m., and 4:00 p.m. to 6:00 p.m. unless approved by the Transportation Director or Designee.

5.1.3 A travel lane shall be defined as ten (10) feet of roadway not obstructed by traffic control devices with a safe motor vehicle operating speed of twenty-five (25) miles per hour.

5.1.4 A travel lane will not be considered as open to traffic until it has been graded reasonably smooth and is paved with a minimum of two (2) inches of asphalt. This shall be considered temporary pavement and shall be removed completely before proceeding with final surfacing.

- 5.1.5 The Contractor shall provide and maintain all required and requested traffic control devices to protect and guide traffic for all work in the construction area.
- 5.1.6 Intersection area shall be defined as all of the area within the right-of-way of intersecting streets, plus two-hundred fifty (250) feet beyond the center of the intersected streets on all legs of the intersection.
- 5.1.7 The Contractor shall maintain all existing traffic signs erect, clean and in full view of the intended traffic at all times. Street name signs at major street intersections shall be maintained erect at all times. If any signs interfere with construction, the Contractor shall notify the Transportation Department at least 48 hours in advance before covering or removing said signage. The Contractor shall be responsible for reinstalling all signs removed or covered and verifying they are correctly placed. The Transportation Department will inspect all signage prior to completion of the project.
- 5.1.8 Local access to all properties on the subject project shall be maintained at all possible times in the form of a safe and reasonable direct route to at least one of the above defined major streets. Whenever local access cannot be maintained, the Contractor shall notify the affected property owner or user and the Engineer at least Seventy-Two (72) hours in advance.
- 5.1.9 The Contractor shall be required to provide a uniformed off-duty City of Glendale police officer to assist with traffic control whenever traffic in any one direction is restricted to one lane at a signalized major intersection or at other locations if it should become necessary in the opinion of the Transportation Director or Designee. If the Contractor chooses to use a police officer at other locations during peak traffic hours or to assist with his other traffic control operations, the cost shall be included in the lump sum for "Traffic Control" and not paid out of the hours allowed for "Off Duty Glendale Police Officer." All requests for off-duty officers will be made through the Glendale Police Department, Off-Duty Work Administrator. The Contractor must provide evidence of workmen's compensation coverage before any officer will be permitted to work.

Measurement for payment of the uniformed off-duty Glendale police officer hours will be made by the actual number of man-hours used for traffic control at signalized major intersections or as approved by the Engineer. Because the quantity of hours is dependent on the Contractors schedule of activities, the unit price bid for this item will be administered as a contingency bid item and any adjustment in hours will not be subject to the 20 percent limitation.

Payment for the off-duty Glendale police officer will be made at the contract unit price bid per hour for OFF DUTY GLENDALE POLICE OFFICER and shall include the net hourly rate of \$35.00 per police officer with a three (3) hour minimum. The net hourly rate shall be increased to include withholding for Federal, State, FICA, Medicare, Workmen's Compensation insurance and any payroll administrative costs.

- 5.1.10 The Contractor shall prepare a traffic control plan for the project and submit it to the City Transportation Director or Designee for review and approval at least fifteen (15) working days prior to the start of construction. The traffic control plan must be submitted through the City of Glendale on-Line Traffic Control Plan application process at www.glendaleaz.com/transportation/TrafficControlForm.cfm. The traffic control plan shall include message boards installed a minimum of seven (7) working days prior to restrictions when requested by the Transportation Director or Designee, additional public notification shall be required for major restrictions that impact adjacent stakeholders. Any changes to the traffic control plan during construction shall be submitted to the City Transportation Director or Designee for approval at least seventy-two (72) hours before implementation.

Payment for this item shall be made at the contract lump sum price for TRAFFIC CONTROL.

- 5.1.11 It is the City's desire to maintain one lane of traffic in each direction on minor streets whenever possible. Should it become imperative for the Contractor to close off a portion of any minor street or reduce the travel way to a single lane, he/she must obtain approval from the City Transportation Director or Designee Seventy-Two (72) hours prior to implementing a traffic control change. He/she must provide all the necessary signs to detour traffic and/or flag person to control traffic for a single lane. The maximum amount of time that the street may be closed is from 9:00 a.m. until 4:00 p.m.
- 5.1.12 Flagger Requirements: All flaggers shall be properly trained and certified by a recognized source, such as the American Traffic Safety Services Association (ATSSA) or National Safety Council, and shall carry with them at all times proof that training and certification requirements have been completed within the last two years.
6. ENERGIZED AERIAL ELECTRICAL POWER LINES: The utility company maintains energized aerial electrical power lines in the immediate vicinity of this project. Do not consider these lines to be insulated. Construction personnel working in proximity to these lines are exposed to an extreme hazard from electrical shock. Contractors, their employees, and all other construction personnel working on this project must be warned of the danger and instructed to take adequate protective measures, including maintaining a minimum ten (10) feet clearance between the lines and all construction equipment and personnel. (See: OSHA Standard 1926.550(a)15.) As an additional safety precaution, Contractors should also be instructed to call the utility company to arrange, if possible, to have these lines de-energized or relocated when the work reaches their immediate vicinity. The cost of such temporary arrangements would be borne by the Contractor. The utility company can often respond to such requests if two days advance notice is given, but some situations may require up to sixty (60) days lead time for relocation or other arrangements.
7. RECORD DRAWINGS: The Contractor shall maintain one set of contract drawings with all changes, deviations, additions and deletions clearly marked thereon. Upon completion of the work, this set of drawings, shall be marked "RECORD DRAWINGS," dated, and delivered to the Engineer prior to approval of the Contractor's final payment request.
8. CONSTRUCTION MATERIALS SAMPLING AND TESTING: The contractor, at their expense, shall provide adequate personnel for construction materials sampling and testing functions as required by the City of Glendale. Proof of certifications of the following requirements shall be provided to the City of Glendale prior to commencement of construction:
- A. LABORATORY TESTING SERVICES: Construction materials testing laboratories must meet the following requirements in order to perform laboratory testing on construction materials samples:
- a. Possess and maintain current AASHTO accreditation (including R18) provided by the AASHTO Materials Reference Laboratory (AMRL), and Cement and Concrete Reference Laboratory (CCRL) in any test methods performed and be currently participating in their respective proficiency programs.
 - b. Concrete strength testing must be performed by a technician currently certified by the American Concrete Institute (ACI) as a "Concrete Strength Testing Technician".
- B. FIELD TESTING AND SAMPLING SERVICES: Field technicians shall be employed by the construction materials testing laboratory noted above and have current "*Field Technician Certification*" from the Arizona Technical Testing Institute (ATTI) and current "*Concrete Field Testing Technician - Grade I*" certification from the American Concrete Institute.
- C. TESTING FREQUENCIES: Laboratory and field testing and sampling shall adhere to the current City of Glendale minimum frequencies (see tables below) formal documentation, records etc. shall be provided to the City in a timely manner and as part of required project

documentation for overall project acceptance. The City reserves the right to utilize independent / additional testing to confirm prior results.

Payment for this item will be made at the contract lump sum price fully complete for CONSTRUCTION MATERIALS SAMPLING AND TESTING.

9. CASH FLOW REPORT: The Contractor shall prepare a Cash Flow Report for projected monthly project cash flow on a City provided form and submit it for approval prior to issuance of the Notice to Proceed. The accumulation of monthly pay estimate costs shall be plotted versus time in accordance with the proposed construction schedule. After approval, the Contractor shall submit an updated Cash Flow Report prior to the receipt of each Progress Payment. Each updated Cash Flow Report shall reflect the Contractor's actual monthly payment versus the actual elapsed contract time.

At the City's request, if the projected quarterly project cash flow varies by more than ten percent of the total contract price, the Contractor shall prepare a revised Cash Flow Report. Each revised Cash Flow Report is subject to approval by the City prior to issuance of the progress payment.

Revisions to the report resulting from Contractor initiated delays or work schedule changes shall be at no cost to the City. Any revisions required by City initiated delays or changes to the work shall be paid as an integral part of the approved Change Order.

10. ALLOWANCE FOR CONSTRUCTION CONTINGENCIES: Bid schedule includes a lump sum contingency allowance. This allowance is at all times the property of the City and is for the sole purpose of reimbursing Contractor for any unforeseen work not apparent at the time of bidding or additional work requested by the CITY OF GLENDALE.

No work anticipated for reimbursement under this Bid Item shall be initiated by Contractor until Contractor, City of Glendale Representative and City of Glendale agree on the scope and cost to perform the additional work. The Contractor shall prepare and submit to City of Glendale Representative a cost itemization and summary for the additional work. City of Glendale Representative and City of Glendale shall review and approve prior to Contractor proceeding with any additional work. Any portion of the stated sum not expended remains the property of the City of Glendale.

Work under this section shall consist of any additional work identified by the owner and contractor due to construction activity. All work under this item shall be itemized as per MAG requirements and deducted from the set amount of \$30,000. All work under this section shall include but is not limited to all necessary materials, tools, layout, survey and labor required to complete each task.

Measurement and payment for this item shall be made on an individual basis per task and as described above. Limit for this item is set at \$30,000 on the bid form, under line item ALLOWANCE FOR CONSTRUCTION CONTINGENCY.

END OF SPECIAL PROVISIONS



Project Life Cycle Cash Flow Schedule

Project No.: 0 Date: _____

Project Name: 0

Company Name: _____

Project Start Date: 0 Project Completion Date: 0

Original Updated Revised

Qtr.	Fiscal Yr.	Estimated		Actual	
		Amount	Accum.	Amount	Accum.
1st	07/13 - 09/13	\$ -	\$ -		
2nd	10/13 - 12/13	\$ -			
3rd	01/14 - 03-14	\$ -			
4th	04/14 - 06/14				
1st	07/14 - 09/14				
2nd	10/14 - 12/14				
3rd	01/15 - 03/15				
4th	04/15 - 06/15				
1st	07/15 - 09/15	\$ -	\$ -	\$ -	\$ -
2nd	10/15 - 12/15	\$ -	\$ -		
3rd	01/16 - 03/16	\$ -	\$ -		
4th	04/16 - 06/16	\$ -	\$ -		
1st	07/16 - 09/16	\$ -	\$ -	\$ -	\$ -
2nd	10/16 - 12/16				
3rd	01/17 - 03/17				
4th	04/17 - 06/17				
1st	07/17 - 09/17				
2nd	10/17 - 12/17				
3rd	01/18 - 03/18	\$ -	\$ -	\$ -	\$ -
4th	04/18 - 06/18				
Totals		\$ -		\$ -	\$ -

* COG's fiscal year is July 1, (current year) through June 30, (following year)

For Engineering Use Only:	
Account No: _____	PO No. _____